

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

RECEIVED

WATER WELL REPORT

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion

OCT 31 1978

STATE OF OREGON
(Please type or print)

WATER RESOURCES DEPT., do not write above this line

SALEM, OREGON

State Well No. 6N/3W-24
State Permit No. _____

(1) OWNER:

Name Michael Bledsoe
Address Rt. 2 Box 2247
Deer Island, Oregon 97054

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Cable ☐ Dug ☐ Driven ☐ Jetted ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐ Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from +2'2" ft. to 96'6" ft. Gage 250
5" Diam. from 90 ft. to 140 ft. Gage 188
" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch-Cut
Size of perforations 3/8 in. by 6 in.
14 perforations from 100 ft. to 140 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller
Yield: 9.3 gal./min. with 84 ft. drawdown after 1 hrs.
Tested with air-rotary at
" 139' " " "
Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m.

Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite
Well sealed from land surface to 32 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 9 sacks
How was cement grout placed? #1 Poured 5 gal. of
1/2" rock. #2 Poured in 5 gal.
of crushed rock. #3 Poured in
Bentonite
Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☒ Yes ☐ No
Type of water? Colored depth of strata 90-96
Method of sealing strata off Cased
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Columbia Driller's well number _____
1/4 1/4 Section 24 T. 6N R. 3W W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 98 ft.
Static level 55 ft. below land surface. Date 10-20-78
Artesian pressure 0 lbs. per square inch. Date 10-20-78

(12) WELL LOG:

Diameter of well below casing 0

Depth drilled 140 ft. Depth of completed well 140 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	2	
Clay Brown	2	16	
Clay Red w/shale	16	20	
Shale + Clay Brown	20	40	
Rock Black + Broken Med.	40	44	
Rock Basalt Black Med.	44	52	
Rock Decomposed Med-Soft	52	60	
Rock Black Med.	60	66	
Rock Red-Brown Soft	66	73	
Rock Decomposed Med.	73	77	
Clay Yellow	77	80	
Rock Black Med-Hard	80	86	
Decomposed Rock Red +	86	91	
Yellow w/clay yellow			
Decomposed Rock Med.	91	99	
Rock Red + Black	99	115	
Rock Red + Yellow	115	120	
Rock Basalt Black Med.	120	140	

Work started 10-19 1978 Completed 10-20 1978
Date well drilling machine moved off of well 10-21 1978

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] J. Stux McShee Date 10-27, 1978
(Drilling Machine Operator)

Drilling Machine Operator's License No. 849

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Dale McShee (Person, firm or corporation) (Type or print)

Address 3032 Allen St. Kelso, Wash.

[Signed] Dale McShee (Water Well Contractor)

Contractor's License No. 424 Date 10-27, 1978

Received Date:

8/25/03

County Well Log ID #

Colu 255

Well Identification Tag #

L-666174

WELL IDENTIFICATION APPLICATION FORM

(please see attached instructions)

✓ **DO NOT COMPLETE THIS FORM IF YOU ARE SHARING THE WELL ON ANOTHER'S PROPERTY**

BUYER/CURRENT LANDOWNER (FOR PROPERTY WELL IS LOCATED ON):

Name: Ron Stocker

Mailing Address: 68684 Bedell Rd.

City: Deer Island State: OR Zip: 97054 Phone: ()

NOTE: Well Identification Tag will be sent to the above address unless otherwise specified above.

RECEIVED

AUG 25 2003

WATER RESOURCES DEPT
SALEM, OREGON

WELL LOCATION:

County: Columbia Well # (designation owner has given to well if multiple wells exist on same property): 0

Township: 6N North or South. Range: 3W East or West. Section: 24 14 14
(circle one) (circle one)

Tax Lot #: 00501 (not the "tax acct.#") Type of Well: water supply monitoring

Address of Well: 68684 Bedell Rd. Deer Island OR 97054
(Number) (Street) (City)

Does this well have a formal water right associated with it? Yes: No:
(If unknown you may contact the Water Rights Information Group at 503-378-3739 extension 201 for research)

If Yes: Application #: Permit #: Certificate #:

(Optional): Latitude Longitude (May sometimes be obtained from Well Log Report)

WELL INFORMATION: (If available, attach copy of driller's well report. If report is not available please complete the following, at a minimum the prior landowner names going back until around the time the well would have been drilled. Prior landowners can be obtained from the County Assessor.)

Start Card #: Approx. Well Construction Date: 10-19-78

Well Constructor: Dale McGhee

Name of Land Owner at Time of Construction (or list of prior landowners) Michael Bledsoe

Well Depth (in feet): 140 Static Water Level (in feet): 55

Diameter of Exposed Well Casing (in inches): 32

Please Return Completed Form to: Well ID Program @ Oregon Water Resources Department
158 12th Street NE - Salem, OR 97301-4172, or fax to 503-378-8130