

Colu
50234

103343

(1) OWNER: Well No. 1
Name JIM MILES
Address 33530 RODNEY RD.
City WARREN St OR Zip 97053

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:

Special Construction	Approval NO	Depth of Compl. Well	200 ft
Explosives used NO	Type	Amount	
HOLE SEAL			
Diam.	From	To	Material
10	0	18	BENTONITE
8	18	75	CEMENT
6	75	200	

Seal placement method C
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection
Casing	6	+2	72		STEEL	WELDED
Liner	4.5	-2	200		PLASTIC	WELDED

Final Location of shoe(s) 72

(7) PERFORATIONS/SCREENS:

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
180	200	1/2	2PFT			LINER

[X] Perf. Method DRILL HOLE
[_] Screens Type Material

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
18		195	1 hr.

Temperature of water 52 Depth Artesian Flow Found ___
Was water analysis done? NO By whom ___
Reason for water not suitable for use ___
Depth of strata ___

(9) LOCATION OF WELL by legal description:
County COLUMBIA Lat. ' ' " Long. ' ' "
Township 5 N Range 1 W WM.
Section 7 SW 1/4 NE 1/4
Tax Lot 3200 Lot Block Subdivision
Street Address of Well (or nearest Address)
CANAAN RD DEER ISLAND, OR 97054

(10) STATIC WATER LEVEL:
85 ft. below land surface. Date 07/24/96
Artesian pressure ___ lb per square in. Date ___

(11) WATER BEARING ZONES:

Depth at which water was first found	135	Est Flow Rate	SWL
From	To		
135	152	18	85

(12) WELL LOG:

Material	Ground elevation	From	To	SWL
TOP SOIL		0	2	
YELLOW CLAY		2	35	
BASALT		35	195	85
BLUE SANDSTONE		195	200	

RECEIVED
AUG 23 1996
WATER RESOURCES DEPT.
SALEM, OREGON

Date started 07/22/96 Completed 07/24/96

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed AMM WWC Number 1480
Date 08/19/96