

STATE OF OREGON  
**Water Supply Well Report**

(as required by ORS 537.765)

COLU 52290  
**COLU**

Received Date: 07-21-2003

Well ID Tag # L 57285

Start Card # 147401

Instructions for completing this report are on the last page of this form.

**(1) Owner** Well Number: 3  
 Name: MAC NELSON  
 GREEN MEADOWS MOBILE HOME PARK  
 Street: PO BOX 645  
 City: SCAPPOOSE State: OR Zip Code: 97056

**(2) Type of Work**  
 New  Alter (Recondition)  Alter (Repair)  
 Deepening  Abandonment

**(3) Drill Method**  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other: UNDERREAMER SYSTEM

**(4) Proposed Use**  
 Domestic  Community  Industrial  Irrigation  Injection  
 Livestock  Thermal Other:

**(5) Bore Hole Construction**  
 Special Standards: Depth of completed well: 84.00 ft.  
 Explosives Used: Amount: Type:  

Hole			Seal			
Diameter	From	To	Mtrl	From	To	Sacks/lbs
10	0	22	BC	0	8	7
8	22	85	CE	8	24	9

  
 How was seal placed? C Other: POURED  
 Back fill placed from: Material:  
 Filter pack from: Size:

**(6) Casing / Liner**  
 Csng/ Shoe Shoe  
 Liner Diameter From To Gauge Mtrl Weld Thrd at used  
 C 6 -1 83 .250 S X 83 In

**(7) Perforation / Screens**  
 Perforations: Csng/  
 Mtrl From To Width Height #Slots Dia. t/pSize Lnr Method  
 Screens:  
 Mtrl From To S Size #Slots Dia. t/pSize Type Gauge

**(8) Well Tests (Minimum testing time is one hour)**  

Type	Yield	Units	Drawdown	Stem at	Duration
A	100.00	G		83	1.00

Temperature of Water: 55.00 F  
 Was water analysis done?  Depth of artesian flow:  
 by whom?  
 Did any strata contain water unsuitable for use?  Too Little  Salty  
 Muddy  Odor  Colored other:  
 Depth of strata:

**(9) Location of Hole by legal description**  
 County: COLU Latitude: Longitude:  
 Township: 3.00 N Range: 1.00 W  
 Section: 7 SWNW Lot: Block:  
 Tax Lot: 400 Subdivision:  
 Street Address of Well (or nearest address):  
 34411 GREEN MEADOW WAY SCAPPOOSE OR 97056  
 MAP, with location identified, must be attached.

**(10) Static Water Level**  
 Feet below land surface: 9.00 Date: 05 / 24 / 2003  
 Artesian Pressure: Date:

**(11) Water Bearing Zones**  
 Depth at which water was first found: 8.00 ft.

From	To	est Flow	swl
8	14	7	8
67	78	60	9
78	84	40	9

**(12) Well Log** Ground Elevation:

Material	From	To	swl
BROWN CLAY SILT	0	4	
SM-MD GRAVEL, COBBLES & BLDRS	4	14	8
TAN PLASTIC CLAY & GRAVEL	14	17	
SAME AND GRAY CLAY	17	19	
BROWN CLAY & ANGULAR GRAVEL	19	26	
MC SM-MD GRAVEL & SAND	26	64	9
SAME BUT MUDDY	64	67	
MC SM-MD GRAVEL & SAND	67	78	9
SAME BUT LESS SAND	78	84	9

Date Started: 05 / 19 / 2003 Date Completed: 05 / 24 / 2003

**(unbonded) Water Well Constructor Certification:**  
 I certify that the work I perform on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to the best knowledge and belief.  
 Signed by: WWC #:  
**(bonded) Water Well Constructor Certification:**  
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
 Signed by: THOMAS R DANNISON JR WWC #: 1679  
 TURNER WELL DRILLING Phone: 503-543-8383