

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 72955

START CARD # W 169475

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name **TAMBLE, ANTHONY**
Address **79884 STEWART CREEK RD**
City **CLATSKANIE** State **OR** Zip **97016**

(2) TYPE OF WORK ☐ New Well
☒ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well **420** ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
6	280	420				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:				☐	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
Liner:	4.5	60	420	☐	☒	☐	☐
				☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☐ None

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS
☒ Perforations Method **DRILL BIT**
☐ Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
361	417		150	7/16	4.5	☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
20		415	ONE

Temperature of water **50** Depth Artesian Flow Found _____

Was a water analysis done? ☒ Yes By whom **DRILLER**

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County **COLUMBIA**
Tax Lot **0700** Lot _____
Township **8N** N or S Range **3W** E or W WM
Section **30** NW 1/4 SW 1/4

Lat _____ " or _____ (degrees or decimal)

Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) **79884 STEWART CREEK RD.**

(10) STATIC WATER LEVEL

232 ft. below land surface. Date **4-14-06**

_____ ft. below land surface. Date _____

Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found **393**

From	To	Estimated Flow Rate	SWL
393	395	20	232

(12) WELL LOG

Ground Elevation _____

Material	From	To	SWL
BASALT GREY	280	336	
BASALT LIGHT BROWN	336	342	
BASALT GREY	342	344	
BASALT BROWN	344	347	
SANDSTONE LIGHT BROWN	347	355	
BASALT GREY	355	367	
BASALT DARK GREY	367	385	
BASALT GREY	385	393	
BASALT GREENISH GREY	393	401	232
BASALT LIGHT GREY	401	411	
BASALT DARK GREY	411	420	

Date Started **APRIL 13, 2006** Completed **APRIL 14, 2006**

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number **1624** Date **4-19-2006**

Signed *Tom Logner*

ORIGINAL - WATER RESOURCES DEPARTMENT

FIRST COPY - CONSTRUCTOR

SECOND COPY - CUSTOMER

06/16/2004

RECEIVED
MAY 16 2006
WATER RESOURCES DEP.
SALEM, OREGON