

STATE OF OREGON
WATER SUPPLY WELL REPORT

COLU 56344

WELL I.D. LABEL# L

Page 1 of 2

START CARD #

ORIGINAL LOG #

156239

1082729

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/15/2026

(1) LAND OWNER

Owner Well I.D.

First Name JEREMY & GWENDOLYN Last Name REBER

Company

Address 14307 SE RIVER ROAD

City MILWAUKIE State OR Zip 97267

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal:

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 150.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	24	Bentonite Chips	0	14	14	S
6	24	150			Calculated	11	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POUR

Backfill placed from 24 ft. to 150 ft. Material PEA GRAVEL

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 7/8/2026 Begin Time 08 30

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	1.5	24	0.250	ST	☒		OUT.	24
L	4		10	12	Sch40	PL		☒		

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type slot Material pvc

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Liner	4	120	150	20		200000	Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	20		145	1

Temperature 48 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 53 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County COLUMBIA Twp 4.00 N N/S Range 2.00 W E/W WM

Sec 34 SE 1/4 of the NW 1/4 Tax Lot 2600

Tax Map Number Lot

Lat ° ' " or 45.78899679 DMS or DD

Long ° ' " or -122.92007866 DMS or DD

☐ Street address of well ☒ Nearest address

NEAR 31505 SIERCKS ROAD, SCAPPOOSE, OR 97056

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/8/2026			73
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 98.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/8/2026	98	100	5			73
7/8/2026	137	140	15			73

(11) WELL LOG

Ground Elevation 285.44 FT

Material	From	To
tan clay	0	10
drk brn claystone w/ cemented gravel	10	23
brn claystone	23	30
white ,brn claystone	30	50
red claystone	50	70
brn claystone	70	80
GRAY SANDSTONE	80	85
brn claystone	85	100
gray, brn basalt	100	117
green gray basalt softer	117	150

Construction

Begin Date 7/6/2026 Begin Time 08 00 End Date 7/8/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1975 Date 7/15/2026

Signed AARON MORLEY (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1480 Date 7/15/2026

Signed ARTHUR MCMULLEN (E-filed)

Drilling Company: MCMULLEN 503-397-2356

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

COLU 56344

7/15/2026

Map of Hole

