

COOS

MAR 21 1990

MAR 23 1990

T30s/R15w/11dd
16053

STATE OF OREGON
WATER WELL REPORT 004475 WATER RESOURCES DEPT.
(as required by ORS 537.765) SALEM, OREGON SALEM, OREGON (START CARD) #

(1) OWNER: HARRY SPENCER Well Number: 39
Name GROWTH UNLIMITED TREE FARM
Address P.O. BOX 291
City LANGLOIS State OR. Zip 97450

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 57'2"
Explosives used Yes No Type Amount

HOLE SEAL Amount
Diameter From To Material From To sacks or pounds
10" 0 18 CEMENT 0 18 800#
6" 18 58

How was seal placed: Method A B C D E
 Other
Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 6" +1 39'11 1/2" .250
Liner:

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:
 Perforations Method TELESCOPE
 Screens Type JOHNSON Material STAINLESS STEEL
From To Slot size Number Diameter Tele/pipe size Casing Liner
38'10" 44'9" .015
44'9" 50'14" .012
50'14" 55'3 1/2" .010
55'3 1/2" 57'2"

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min Drawdown Drill stem at Time
42 6'9" @ 53' 1 hr.
Temperature of water 52° Depth Artesian Flow Found
Was a water analysis done? Yes By whom
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other
Depth of strata:

(9) LOCATION OF WELL by legal description:
County COOS Latitude Longitude
Township 30S N or S, Range 15W E or W, WM.
Section 11 SE 1/4 SE 1/4
Tax Lot 1600 Lot Block Subdivision
Street Address of Well (or nearest address) CROFT ROAD -
OFF OF 101 SOUTH.

(10) STATIC WATER LEVEL:
25'6" ft. below land surface. Date 3/13/90
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 25'
From To Estimated Flow Rate SWL
23' 55' 80 25'6"

(12) WELL LOG: Ground elevation 300'
Material From To SWL
CLAY, BROWN 0 6
SAND w/ GRAVEL, BROWN 6 18
GRAVEL w/ SAND, MED., BROWN 18 20
GRAVEL w/ SAND, MED., GRAY 20 23
GRAVEL w/ SAND, MED., RED 23 24 25'6"
SAND w/ GRAVEL, FINE, BROWN 24 28
CLAY w/ SAND, BROWN 28 30
SAND w/ GRAVEL, FINE, BROWN 30 45
GRAVEL w/ SAND, MED., BROWN 45 50
SAND, MED., BROWN 50 55
CLAY, GRAY 55 58

Date started 3/12/90 Completed 3/20/90

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
WWC Number
Signed Date

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
WWC Number 1493
Signed Jim Mack Date 3/20/90