

COOS
51625

MAY 26 2000

28-14-16

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)WATER RESOURCES DEPT.
SALEM, OREGON

WELL I.D. # L-34011

START CARD # 123846

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Well Number 708

Name RICK Sheasby
Address 1019 Fredericks Street
City Woodland State CA Zip 95774

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 620 ft.Explosives used ☐ Yes ☒ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	62	Bentonite	0	40	29 54

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other Poured from Surface

Backfill placed from ft. to ft. Material

Gravel placed from 40 ft. to 60 ft. Size of gravel 10/20

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 5"	1	55'0"	160"	☐	☒	☒	☐
6"	1'4"	4'	.250	☒	☐	☐	☐
(Protective Casing)				☐	☐	☐	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ PerforationsMethod Attached to Casing☒ ScreensType Nagoka V-wire Material SS

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
55'0"	61'0"	10/14	-	5"	Pipe	☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump☐ Bailer☐ Air☐ Flowing
☐ Artesian

Yield gal/min

Drawdown

Drill stem at

Time

7.5

4'

60

1 hr.

Temperature of water 52° Depth Artesian Flow FoundWas a water analysis done? ☒ Yes By whom BW+SDid any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County COOS Latitude Longitude
Township 28 N or S Range 14 E or W. WM.
Section 16 SW 1/4 NE 1/4
Tax Lot 815 Lot Block Subdivision
Street Address of Well (or nearest address) Sunny Loop Way
Glennwood Est. Barndon OR

(10) STATIC WATER LEVEL:

52' ft. below land surface.Date 5/18/00

Artesian pressure lb. per square inch.

Date

(11) WATER BEARING ZONES:

Depth at which water was first found 52'

From	To	Estimated Flow Rate	SWL
52	60	7.5	52

(12) WELL LOG:

Ground Elevation +/- 300'

Material	From	To	SWL
Topsail	0	2	
Cemented Sand Brown	2	3	
Sand Fine Brown	3	18	
Sand Orange	18	19	
Sand Fine Brown	19	21	
Sandy Clay White	21	22	
Sand Fine-med Tan	22	26	
Sandy Clay Tan	26	28	
Sand Fine-CRS Brown	28	40	
Sand Fine-CRS w/ Fine	40	47	
Gravel Gray Brown			
Sand Fine-CRS w/ Gravel	47	52	
Fine-med Gray Brn			
Gravel Fine-CRS Gray	52	60	
Clay Orange	60	61	
Clay Gray	61	62	

Date started 5/17/00Completed 5/18/00

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Barndon Well+Septic Co Inc Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number

Signed Jim Madril M6WC Date 5/23/00