

29-14-08

COOS
52725

WELL I.D. # L 57032
START CARD # 147882

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(1) **LAND OWNER**
Name Grant Family Farms (Steve Grant) Well Number 917
Address PO Box 765
City Bandon State OR Zip 97411

(2) **TYPE OF WORK**
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) **DRILL METHOD:**
 Rotary Air Rotary Mud Cable Auger
 Other _____

(4) **PROPOSED USE:**
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) **BORE HOLE CONSTRUCTION:**
Special Construction approval Yes No Depth of Completed Well 51' ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	51	Bentonite	0	28	20 SX

How was seal placed: Method A B C D E
 Other Poured from surface

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 26 ft. to 51 ft. Size of gravel 8/12

(6) **CASING/LINER:**

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	40'	160#	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6"	46	51	160#	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(Tail Pipe)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Liner: 8"	+1'4"	4'	1250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(Protective Casing)				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used Inside Outside None
Final location of shoe(s) _____

(7) **PERFORATIONS/SCREENS:**

Perforations Method Attached to casing
 Screens Type Johnson V-wire Material SS

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
40/11	46	1050		6"	Pipe	<input type="checkbox"/>	<input type="checkbox"/>

(8) **WELL TESTS: Minimum testing time is 1 hour**

Yield gal/min	Drawdown	Drill stem at	Time
58'	20' 5"	43	1 hr.
58	20' 5"	43	2 hrs.

Temperature of water 52° Depth Artesian Flow Found _____

Was a water analysis done? Yes By whom _____

Did any strata contain water not suitable for intended use? Too little

Salty Muddy Odor Colored Other _____

Depth of strata: _____

Bandon Well & Septic Co., Inc.

(9) **LOCATION OF WELL by legal description:**
County Coos Latitude _____ Longitude _____
Township 29 N or S Range 14 E or W W.M.
Section 08 SE 1/4 NE 1/4
Tax Lot 200 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 5411 Rosal Rd. Bandon

(10) **STATIC WATER LEVEL:**
10'6" ft. below land surface. Date 9/25/03
Artesian pressure _____ lb. per square inch Date _____

(11) **WATER BEARING ZONES:**
Depth at which water was first found 10'6"

From	To	Estimated Flow Rate	SWL
10'6"	45	+/- 65	10'6"

(12) **WELL LOG:**
Ground Elevation +1-300'

Material	From	To	SWL
Sandy Clay Tan brn	0	2	
Peat brown	2	4	
Sand Fine-med w/ gravel	4	39	
Fine Gray			
Gravel Fine - CRS w/ sand	39	45	
Fine - CRS Orange brown			
Clay Gray	45	51	

RECEIVED
SEP 30 2003
OCT 31 2003
WATER RESOURCES DEPT
SALEM, OREGON

Date started 9/10/03 Completed 9/25/03

(unbonded) **Water Well Constructor Certification:**
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed Charlie Leary WWC Number 1759 Date 9/26/03

(bonded) **Water Well Constructor Certification:**
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed John M. G. R. McGraw WWC Number 1493 Date 9/26/03