

WELL LABEL # L 80263

START CARD # 182710

(1) LAND OWNER

Owner Well I.D. 1148

First Name Paul Last Name Sogn
Company
Address 628 St Andrews Loop
City Creswell State OR Zip 97426

(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)

Depth of Completed Well 56.00 ft.

BORE HOLE			SEAL				sacks/
Dia	From	To	Material	From	To	Amt	lbs
12.25	0	56	Bentonite	0	26	26	S
6	56	60					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Pour from surface

Backfill placed from ft. to ft. Material

Filter pack from 26 ft. to 46 ft. Material Sand Size 10/20

Explosives used: ☐ Yes Type Amount

(6) CASING/LINER

Casing	Liner	Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
☒	☐	8	☒	1.16	41	Sch40	☐	☒	☒	☐
☐	☐	8	☐	51	56	Sch40	☐	☒	☒	☐
☐	☐	10	☒	1.25	3	.250	☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)

Temp casing ☐ Yes Dia From To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Johnson V-Wire Material Stainless Steel

Perf/	Casing/	Screen	Dia	From	To	Scrn/slot	Slot	# of	Tele/
Screen	Liner					width	length	slots	pipe size
Screen			8	41	47	.031			8
Screen			8	47	51	.051			8

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
25	13	52	1
30	18	52	2

Temperature 53 °F Lab analysis ☒ Yes By Bandon Well & Pump Co.

Water quality concerns? ☐ Yes (describe below)

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County Coos Twp 29.00 S N/S Range 14.00 W E/W WM

Sec 5 NW 1/4 of the NW 1/4 Tax Lot 902

Tax Map Number Lot

Lat ° ' " or DMS or DD

Long ° ' " or DMS or DD

☒ Street address of well ☐ Nearest address

no # vacant, Rosa Road, Bandon (in back of 54651 Rosa Road)

(10) STATIC WATER LEVEL

Date SWL(psi) + SWL(ft)

Existing Well / Predeepening			
Completed Well	10-20-2006		26

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES Depth water was first found 26

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
10-18-2006	26	51	30		26

(11) WELL LOG

Ground Elevation 300

Material	From	To
Sandy clay brown	0	2
Cemented sand brown	2	5
Sand fine tan	5	11
Sandy clay orange	11	12
Sand fine tan	12	14
Sandy clay orange	14	15
Sand fine tan	15	33
Sandy clay gray	33	35
Sand fine medium w/gravel fine gray	35	47
Gravel fine-medium w/ sand fine-medium gray	47	51
Clay gray	51	53
Claystone gray	53	60

Date Started 09-12-2006 Completed 10-20-2006

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1759 Date 10-24-2006

Electronically Filed

Signed CHRISTOPHER L KERSEY (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1493 Date 10-24-2006

Electronically Filed

Signed JAMES A MACK SR (E-filed)

Contact Info (optional) BANDON WELL & PUMP COMPANY (541) 347-7867

