

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

COOS 57360

WELL I.D. LABEL# L 129838
START CARD # 1039322
ORIGINAL LOG #

11/27/2018

(1) LAND OWNER

Owner Well I.D. 1745 (SR3)

First Name MICHAEL Last Name KEISER
Company BALLY BANDON LLC (3)
Address 875 N MICHIGAN AVE # 3920
City CHICAGO State IL Zip 60611

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrld
Material From To Amt sacks/lbs
Seal:

(3) DRILL METHOD

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☐ Domestic ☒ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 92.25 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
20	0	4	Bentonite	0	38	41	S
12.25	4	93			Calculated	28.32	
					Calculated		

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other POUR FROM SURFACEBackfill placed from ft. to ft. Material Filter pack from 38 ft. to 93 ft. Material SAND Size 6/9Explosives used: ☐ Yes Type Amount **(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount Actual Amount

(6) CASING/LINER

Casing Liner Dia + From To Gauge Stl Plstc Wld Thrld
☒ ☐ 10 ☒ 1.5 4 .250 ☒ ☐ ☐ ☐
☒ ☐ 8 ☒ 1 69.25 Sch40 ☐ ☒ ☒ ☐
☒ ☐ 8 ☐ 86.25 92.25 Sch40 ☐ ☒ ☒ ☐
☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐
Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)
Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENSPerforations Method Screens Type Johnson V-Wire Material Stainless Steel

Perf/ Screen	Casing/ Liner	Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ pipe size
Screen	Casing	8	69.25	86.25	.071			8

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
65	8.7	85	4

Temperature 54 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 162 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County COOS Twp 27.00 S N/S Range 14.00 W E/W WM
Sec 20 SW 1/4 of the NW 1/4 Tax Lot 100
Tax Map Number Lot
Lat ° ' " or 43.21784402 DMS or DD
Long ° ' " or -124.39205173 DMS or DD
☒ Street address of well ☐ Nearest address

NO# WHISKEY RUN RD, BANDON

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	11/20/2018			59.3
Flowing Artesian? ☐ Dry Hole? ☐				

WATER BEARING ZONESDepth water was first found 58.75

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
11/7/2018	58.75	86	110			58.75
11/12/2018	59	86	110			59
11/19/2018	59.18	86	110			59.18
11/20/2018	59.35	86	110			59.35

(11) WELL LOGGround Elevation 150.00

Material	From	To
Sandy topsoil	0	2
Cemented sand orange brown	2	4
Sand f-m brown orange	4	5
Sandy clay w/sand f-m yellow brown	5	7
Sand f-m brown	7	12
Cemented sand brown	12	20
Sand f-m orange brown	20	25
Sand f-m w/cemented lenses brown	25	27
Sand f-m w/sandy clay & wood tan brown	27	34
Sand f-m brown gray	34	55
Sand f-m w/cemented sand brown orange	55	57
Sand f-c brown *	57	69
Gravel f-m w/sand c-f brn gray loss cir*	69	84
Gravel f-c w/sand c-f & clay brn gray20	84	86
Sandy clay gray	86	87
Claystone gray	87	88
Sandstone gray	88	93

Date Started 6/25/2018 Completed 11/20/2018**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date Signed **(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1493 Date 11/27/2018Signed JAMES MACK SR (E-filed)Contact Info (optional) BANDON WELL & PUMP CO. (541) 347-7867

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

(2a) PRE-ALTERATION

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
					○ ○			
					○ ○			
					○ ○			
					○ ○			

Material	From	To	Amt	sacks/lbs

(5) BORE HOLE CONSTRUCTION

BORE HOLE			SEAL			sacks/	
Dia	From	To	Material	From	To	Amt	lbs
					Calculated		
					Calculated		
					Calculated		
					Calculated		

FILTER PACK

From	To	Material	Size

(6) CASING/LINER

Casing Liner	Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
									
									
									
									

(7) PERFORATIONS/SCREENS

[illegible]

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
---------------	----------	-----------------------	---------------

Water Quality Concerns

[illegible]

(10) STATIC WATER LEVEL

[illegible]

(11) WELL LOG

[illegible]

Comments/Remarks

[illegible]

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

COOS 57360

11/27/2018

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 43.21784402 Datum: WGS84

Longitude: -124.39205173

Township/Range/Section/Quarter-Quarter Section:
WM 27S 14W 20 SWNW

Address of Well:

NO# WHISKEY RUN RD, BANDON

Well Label: 129838

Printed: November 27, 2018

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

