

STATE OF OREGON
WATER SUPPLY WELL REPORT

COOS 58102

WELL I.D. LABEL# L

143669

START CARD #

1055911

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/15/2022

(1) LAND OWNER

Owner Well I.D. 1999

First Name GARY

Last Name CANNON

Company

Address 47338 FLORES LAKE LOOP

City LANGLOIS

State OR

Zip 97450

(2) TYPE OF WORK☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal: From To Amt sacks/lbs

(3) DRILL METHOD
☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other
(4) PROPOSED USE
☐ Domestic ☒ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other
(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)

Depth of Completed Well 60.00 ft.

BORE HOLE			SEAL			sacks/	
Dia	From	To	Material	From	To	Amt	lbs
10	0	60	Bentonite	0	30	15	S
6	60	63			Calculated	14.1	
					Calculated		

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other POUR FROM SURFACE

Backfill placed from ft. to ft. Material

Filter pack from 30 ft. to 60 ft. Material SAND Size 8/12

Explosives used: ☐ Yes Type Amount**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount

Actual Amount

(6) CASING/LINER

Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Johnson V-Wire

Material Stainless Steel

Perf/	Casing/	Screen	Dia	From	To	Scrn/slot	Slot	# of	Tele/
Screen	Liner					width	length	slots	pipe size
Screen	Casing		6	45	55	.04			6

(8) WELL TESTS: Minimum testing time is 1 hour☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
54	27	60	1

Temperature 54 °F Lab analysis ☐ Yes ByWater quality concerns? ☐ Yes (describe below) TDS amount 42 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County COOS Twp 30.00 S N/S Range 15.00 W E/W WM

Sec 12 SE 1/4 of the NW 1/4 Tax Lot 400

Tax Map Number Lot

Lat ° ' " or 42.99259103 DMS or DD

Long ° ' " or -124.42658996 DMS or DD

☒ Street address of well ☐ Nearest address

95033 CROFT LAKE LANE, BANDON

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/13/2022			19.2
Flowing Artesian? ☐ Dry Hole? ☐				

WATER BEARING ZONES

Depth water was first found 19.16

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
3/11/2022	19.16	55	55			19.16

(11) WELL LOG

Ground Elevation 100.00

Material	From	To
Topsoil	0	2
Cemented sand orange brown	2	8
Sand f-m brown	8	16
Sand f-m w/sandy clay tan	16	42
Sand f-c w/gravel f-m orange brown	42	50
Cemented sand orange brown	50	51
Gravel f-c w/fractured claystone & wood	51	55
Claystone gray	55	56
Sandstone gray	56	63
Drilled 6" test hole to 63' to grab samples for sieve analysis & open hole		

Date Started 3/11/2022

Completed 7/13/2022

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1493 Date 7/15/2022

Signed JAMES MACK SR (E-filed)

Contact Info (optional) Bandon Well & Pump Co (541) 347-7867

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

COOS 58102

7/15/2022

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 42.99259103 Datum: WGS84

Longitude: -124.42658996

Township/Range/Section/Quarter-Quarter Section:
WM30.00S15.00W12SENW

Address of Well:

5995033 CROFT LAKE LANE, BANDON

Well Label: 143669

Printed: July 15, 2022

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

