

STATE OF OREGON
WATER SUPPLY WELL REPORT

COOS 58903

WELL I.D. LABEL# L

160781

START CARD #

1083326

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/4/2026

(1) LAND OWNER

Owner Well I.D. 2299

First Name STAN

Last Name GORDON

Company

Address 2303 W. PINE DR.

City ASHLAND

State OR

Zip 97520

(2) TYPE OF WORK☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTIONSpecial Standard ☒ (Attach copy)

Depth of Completed Well 23.91 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	24	Bentonite Chips	0	18.5	21	S
					Calculated	8.79	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POUR FROM SURFACE

Backfill placed from ft. to ft. Material

Filter pack from 18.5 ft. to 24 ft. Material SAND Size 12/20

Explosives used: ☐ Type Amount

Seal Placement Begin Date 9/2/2026 Begin Time 15:00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	6	☒ 1.5 4 0.250	ST	☒			
C	5	☒ 1 18.91 SDR26	PL	☒			

Temp casing ☒ Yes Dia 10 From + ☒ 2 To 18**(7) PERFORATIONS/SCREENS**

Perforations Method

Screens Type Johnson V-Wire Material Stainless Steel

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Casing	5	18.91	23.91	.012			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	10		23	1

Temperature 55 °F Lab analysis ☐ Yes ByWater quality concerns? ☐ Yes (describe below) TDS amount 71 ppm

From To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County COOS Twp 29.00 S N/S Range 15.00 W E/W WM

Sec 12 NE 1/4 of the NE 1/4 Tax Lot 700

Tax Map Number Lot

Lat ° ' " or 43.08058580 DMS or DD

Long ° ' " or -124.41657376 DMS or DD

☒ Street address of well ☐ Nearest address

87538 DAHL LN. BANDON

(10) STATIC WATER LEVEL

	Date	SWL(psi)	+	SWL(ft)
Existing Well / Pre-Alteration				
Completed Well	9/3/2026			7.16
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 7.16

SWL Date	From	To	Est Flow	SWL(psi)	+	SWL(ft)
9/2/2026	7.16	21	10			7.16

(11) WELL LOG

Ground Elevation 73.91 FT

Material	From	To
Topsoil	0	1
Sandy clay brown	1	3
Sand fine brown	3	7
Sandy clay brown	7	11
Sand fine brown	11	13
Gravel f-m w/sand f-c brown	13	17
Sand f-c w/gravel f-m brown	17	20
Gravel f-m w/silty clay gray & wood	20	21
Claystone gray	21	24

Construction

Begin Date 9/2/2026 Begin Time 11:00 End Date 9/3/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2068 Date 9/4/2026

Signed JAMES MACK JR (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1493 Date 9/4/2026

Signed JAMES MACK SR (E-filed)

Drilling Company: Bandon Well & Pump Co. (541) 347-7867 JR

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

COOS 58903

9/4/2026

Map of Hole

