

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
DEC 20 1965
STATE ENGINEER
SALEM OREGON

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

State Well No. 15/15-32

State Permit No.

(1) OWNER:

Name Clyde Davis
Address Phuwell Butte One. 91153

(2) LOCATION OF WELL:

County Crook Driller's well number #2
1/4 1/4 Section 32 T. 15S R. 15E W.M.
Bearing and distance from section or subdivision corner 15E

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☒ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 11.0 ft. Gage 250
6" Diam. from 0 ft. to 18.7 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Pectylene cut
Size of perforations 12 in. by 3/8 in. 6" P.P.C.
100 perforations from 18.5 ft. to 100 ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____ Model No. _____
_____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite
Depth of seal 25 ft. Was a packer used? No
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☒ Yes ☐ No 8"
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level 42 ft. below land surface Date Nov 3/64
Artesian pressure none lbs. per square inch Date Nov 3/64

Is this a duplication? No WSB

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Owner
Yield: 50 gal./min. with 25 ft. drawdown after 1 hrs.

Bailer test gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow g.p.m. Date _____

Temperature of water 58 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 294 ft. Depth of completed well 294 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
top soil clay and sand	0	1
Clay and red rock	0	8
Broken red rock	8	22
Yellow clay and opalite	22	105
Opalite boulders	105	106
Broken opalite and clay	106	185
Yellow clay interspersed with thin seams of grey sedimentary rock	185	250
grey rock and beams	250	294
opposite gravel and sand	294	

Work started 6/26/1964 Completed 11/3/1964
Date well drilling machine moved off of well 11/15/1964

(13) PUMP:

Manufacturer's Name _____
Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Brandt Drilling Co.
(Person, firm or corporation) (Type or print)

Address 675 Crestview Rd.

Drilling Machine Operator's License No. 189

[Signed] C. H. Brandt
(Water Well Contractor)

Contractor's License No. 283 Date 12/5/1964

(USE ADDITIONAL SHEETS IF NECESSARY)