

RECEIVED

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

APR 29 1988

CROO

2097

153/16E-566

(1) OWNER:

Name CROOK COUNTY PARKS & REC. SALEM, OREGON
Address 400 E THIRD
City PRINEVILLE State OR. Zip 97154

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Depth of Completed Well 240 ft.

Special Standards date of approval —

HOLE			SEAL			Amount
Diameter	From	To	Material	From	To	sacks or pounds
10	0	160	CEMT	0	160	2 1/2 YARDS
6"	160	240				

How was seal placed? Method ☐ A ☐ B ☐ C ☐ D ☐ E

☐ Other POURED THRU TRAMIE APC

Backfill placed from — ft. to — ft. Material —

Gravel placed from — ft. to — ft. Size of gravel —

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+2	240	1250	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) —

(7) PERFORATIONS/SCREENS:

☒ Perforations

Method TORCH

☐ Screens

Type — Material —

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
225	240	1/16	150	6"		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump

☐ Bailor

☐ Air

☐ Flowing Artesian

Yield gal/min

Pumping level

Drill stem at

Time

1/4 hr

1 hr

140

80'

4hrs

Temperature of water 65

Depth Artesian Flow Found 225

Was a water analysis done? ☐ Yes By whom —

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other —

Depth of strata: —

(9) LOCATION OF WELL by legal description:

County CROOK Latitude — Longitude —
Township 75S N or S Range 16E E or W, WM.
Section 5 N.W. 1/4 N.W. 1/4
Tax Lot — Lot — Block — Subdivision —
Street Address of Well (or nearest address) 1ST STREET AND N. COURT DAVIDSON BALL PARK

(10) STATIC WATER LEVEL:

32 ft. below land surface. Date 4-27-88

Artesian pressure — lb. per square inch. Date —

(11) WELL LOG:

Ground elevation 2400

Material	From	To	WB?	SWL
Top Soil	0	4		
GRAVEL & CLAY	4	6		
BROWN CLAY	6	22		
SANDY w/B GRAVEL	22	46		
FINE SILT CLAY	46	142		
STICKY BLACK CLAY	142	225		
w/B SAND-COARSE	225	235		
BROWN CLAY	235	240	w/B	32'

Date started 4-17-88 Completed 4-21-88

(unbonded) Water Well Constructor Certification:

I constructed this well in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed — Date —

(bonded) Water Well Constructor Certification:

I accept responsibility for construction of this well and its compliance with all Oregon water well standards. This report is true to the best of my knowledge and belief.

Signed Curt Clauson Date 4-27-88

Company Clauson Well Drilling Co. Job No. 2588