

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

CROO
2303
CROO 2303

JUL 18 1988

155/16E-20cb

(1) OWNER: Lloyd Pettinger
Name: Lloyd Pettinger
Address: P.O. Box 6673
City: BROOKINGS, ORE. State: Zip: 97745
Owner's Well Number:

(2) TYPE OF WORK:
☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:
Depth of Completed Well: 460' ft.
Special Standards date of approval:

HOLE Diameter	From	To	SEAL Material	From	To	Amount sacks or pounds
10"	0	100	Cement	0	100	1 yd
8"	100	460				

How was seal placed? Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other: Pumped via Tremie Pipe
Backfill placed from _____ ft. to _____ ft. Material: _____
Gravel placed from _____ ft. to _____ ft. Size of gravel: _____

(6) CASING/LINER:
Casing: Diameter 6" From +1 To 100 Gauge 750 Steel ☒ Plastic ☐ Welded ☒ Threaded ☐
Liner: 5" OD 3 460 Steel ☐ Plastic ☒ Welded ☐ Threaded ☐

Local location of shoe(s):

(7) PERFORATIONS/SCREENS:
☒ Perforations Method: SAW
☐ Screens Type: Material:
From To Slot size Number Diameter Tele/pipe size Casing Liner
200 460 1/8 200 5" ☐ ☒

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☒ Bailer ☐ Air ☐ Flowing
Yield gal/min Pumping level Drill stem at Time 1/2 hr
3 gpm Complete 2 hr

Temperature of water 60 Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County: Crook Latitude: Longitude: _____
Township: 153 N or S, Range: 16E E or W, WM.
Section: 20 1/4 SW 1/4 Subdivision: Highlands
Tax Lot: 1516 Lot: Block: 1800
Street Address of Well (or nearest address): End of Senic Dr. Pineville, Or.

(10) STATIC WATER LEVEL:
200 ft. below land surface. Date: 6-23-88
Artesian pressure _____ lb. per square inch. Date: _____

(11) WELL LOG: Ground elevation _____

Material	From	To	WB?	SWL
Top Soil	0	3		
BROKEN ROCK	3	81		
TAN CLAY	81	130		
Blue CLAYSTONE	130	256	WB	200'
TAN CLAYSTONE	256	300		
Blue CLAYSTONE	300	460		

Date started: 6-19-88 Completed: 6-24-88

(unbonded) Water Well Constructor Certification:
I constructed this well in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed: _____ Date: _____

(bonded) Water Well Constructor Certification:
I accept responsibility for construction of this well and its compliance with all Oregon water well standards. This report is true to the best of my knowledge and belief.

Signed: Curt Clauson Date: 6-24-88

Company: CLAUSON Well Drilling Co. Job No. 2587

RECEIVED
NO 2587

JUL 21 1988

WATER RESOURCES DEPT.
SALEM, OREGON

"START CARD"
NOTICE OF BEGINNING OF WELL CONSTRUCTION
 (as required by ORS 537.762)

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and
Mailing Address

Lloyd Pettinger
P.O. Box 6673
BROOKINGS, OR. 97415

Proposed Commencement Date 6-20-88

Proposed Well Depth 300, Diameter 8"
 and Use:

☐ Domestic
☐ Thermal

☒ Community
☐ Injection

☐ Industrial
☐ Other

☐ Irrigation

Proposed Well Location: County CROOK

Township 15^S (N or S) Range 16^E (E or W) Section 20

At least 2
of these
must be
provided

1. N.W. 1/4 of S.W. 1/4 of above section

2. street address of Semie DR.
 well location

3. tax lot number of well location #1516 #1800

4. attach approved map with location identified.
 (see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

x N/A
 Owner's Signature

x Curt Clawson
 Bonded Water Well Constructor

OWNER
 Title

License No. 741

6-17-88
 Date

Company CLAWSON WELL DRILLING

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.

RECEIVED

DATE 6-17-88

WATER MASTER DISTRICT #11

BY smj