

RECEIVED WATER WELL REPORT

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

SEP 15 1981

STATE OF OREGON
(Please type or print)

WATER RESOURCES DEPT. Write above this line)
SALEM, OREGON

State Well No. 15516E-256C

State Permit No.

(1) OWNER:

Name Walter Majer
Address 603 NE 94th
Portland, OR 97220

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

6" Diam. from +1.5 ft. to 18.5 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations	in. by	in.
_____ perforations from _____	_____	_____ ft. to _____ ft.
_____ perforations from _____	_____	_____ ft. to _____ ft.
_____ perforations from _____	_____	_____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" NO WATER "

Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m.

Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used PORTLAND CEMENT
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal _____ sacks
How was cement grout placed? Pumped

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County CROOK Driller's well number _____
SW 1/4 NW 1/4 Section 25 T.15 S.R. 16 E W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found _____ ft.
Static level NO WATER ft. below land surface. Date _____
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 340 ft. Depth of completed well 336 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
DARK BROWN CLAY + STONES	0	2	
Dark Gray Basalt	2	218	
Tan Silica + Basalt	218	226	
Dark Gray Basalt	226	245	
Pink + Tan Silica + Basalt	245	253	
Dark Gray Basalt	253	301	
Tan Silica + Basalt	301	308	
Dark Gray Basalt	308	314	
Dark Gray Basalt - slightly broken	314	320	
Tan Silica + Basalt	320	334	
Dark Gray Basalt - Broken	334	340	

CAVING FROM
334 - 340 Feet

CEMENTED + PLASTERED 5 TIMES

TEMP ABANDONED

Work started 3-2 1981 Completed 3-25 1981

Date well drilling machine moved off of well 3-26 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Robert Pilcher Date 9-13 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 764

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name PILCHER WELL DRILLING
(Person, firm or corporation) (Type or print)

Address 577 S. Knight, Prineville, OR

[Signed] Robert Pilcher
(Water Well Contractor)

Contractor's License No. 698 Date Sept. 13 1981