

NOTICE TO WATER WELL CONTRACTOR
The original and five copies
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

Do not write above this line

NOV 21 1968

SALEM, OREGON

CROO
2868

State Well No.

17/24-15adb

State Permit No.

G 5342

(1) OWNER:

Name James Leyton
Address Laurel, Oregon 97751

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

10" Diam. from 1 ft. to 250 ft. Gage 250

" Diam. from " ft. to " ft. Gage "

" Diam. from " ft. to " ft. Gage "

PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Cutting Torch

Size of perforations 1/4 in. by 8 in.

150 perforations from 60 ft. to 80 ft.

150 perforations from 160 ft. to 180 ft.

300 perforations from 220 ft. to 250 ft.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from " ft. to " ft.

Diam. Slot size Set from " ft. to " ft.

(8) WATER LEVEL: Completed well.

Static level 45 ft. below land surface Date 11-8-68

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 100 gal./min. with 15 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water 58 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Bentonite

Depth of seal 20 ft.

Diameter of well bore to bottom of seal 13 in.

Were loose strata cemented off? ☐ Yes ☒ No Depth

Was a drive shoe used? ☐ Yes ☒ No

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from " ft. to " ft.

(11) LOCATION OF WELL:

County Crater Driller's well number
1/4 1/4 Section 15S T. 17S R. 24E W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing

Depth drilled 250 ft. Depth of completed well 250 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
<u>Sapwood (Clay)</u>	<u>0</u>	<u>10</u>	
<u>Brown Clay + Sand</u>	<u>10</u>	<u>60</u>	<u>45</u>
<u>Green Clay</u>	<u>60</u>	<u>170</u>	
<u>Brown Clay - Gravel</u>	<u>170</u>	<u>200</u>	
<u>Green Clay</u>	<u>200</u>	<u>250</u>	

Work started 10-18 1968 Completed 11-8 1968

Date well drilling machine moved off of well 11-8 1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] W. J. Dineen Date 11-20, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 487

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Chris Well Drilling
(Person, firm or corporation) (Type of print)

Address Prineville

[Signed] Dick Atkins
(Water Well Contractor)

Contractor's License No. 260 Date 11/20, 1968