

RECEIVED

DEC 27 1995

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT. (START CARD) # 67410
SALEM, OREGON

CR50
50101

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number _____
Name Happy Camp Campground
Address 11712 S. Davis Loop
City Prineville State Ore Zip 97754

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other _____

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 330 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
12"	0	20'	Bent.	0	19'	15sks
8"	20'	330'				

How was seal placed: Method A B C D E
 Other poured
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

Casing/Liner	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing	8"	+1'	20'	25	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner	6"	-10'	330'		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
 Perforations Method factory
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
310'	330'	1/8x3	235	6"		<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing
Yield gal/min _____ Drawdown _____ Drill stem at _____ Time _____
100+ 0 330' 1 hr.

Temperature of water 53 Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Crook Latitude _____ Longitude _____
Township 16S N or S Range 16E E or W. WM.
Section 9 SW 1/4 NE 1/4
Tax Lot 418 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Happy Camp
11712 S. Davis Loop

(10) STATIC WATER LEVEL:
225' ft. below land surface. Date 12-18-95
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 225'

From	To	Estimated Flow Rate	SWL
225'	330'	100+	225'

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
sandy top soil	0	12'	
brkn rock-brwn clay	12'	31'	
Fract gray lava	31'	155'	
brkn rock congl brwn clay	155'	247'	225'
fract gray lava	247'	291'	291'
brkn rock congl	291'	330'	

Date started 12-13-95 Completed 12-18-95

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
WWC Number 1658
Signed John Skille Date 12-26-95