

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 77296

START CARD # 182410

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number
Name Old Towne Investments
Address P.O. Box 1521
City Prineville State OR Zip 97754

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 305 ft.
Explosives used: ☐ Yes ☒ No Type Amount

BORE HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds
10"	0	40	Bentonite	0	40	35 sacks
6"	40	305	none			

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Poured in Day
Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	0	305	250	☒	☐	☒	☐
Liner: none				☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s)

(7) PERFORATIONS/SCREENS Method Cutting back
☒ Perforations ☐ Screens Type Material

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
300	305	1/2 x 6	40	6"		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
15	40'		4 Hrs

Temperature of water 63 Depth Artesian Flow Found
Was a water analysis done? ☐ Yes By whom
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
Depth of strata:

(9) LOCATION OF WELL (legal description)

County Clackamas
Tax Lot 47604 Lot
Township 24 N of S Range 15 E or W WM
Section 23 NE 1/4 SE 1/4 1/4

Lat " or (degrees or decimal)
Long " or (degrees or decimal)

Street Address of Well (or nearest address) 3901 NW Elliott Lane
Prineville

(10) STATIC WATER LEVEL

60 ft. below land surface. Date 10/15/06
 ft. below land surface. Date
Artesian pressure lb. per square inch Date

(11) WATER BEARING ZONES

Depth at which water was first found 300'

From	To	Estimated Flow Rate	SWL
300	305	15 gpm	60'

(12) WELL LOG

Material	From	To	SWL
Topsoil	0	2	
Brown sand & clay	2	20	
Yellow clay & gravel	20	30	
Black sand & clay	30	300	
Gravel	300	305	60'

RECEIVED

NOV 02 2006

WATER RESOURCES DEPT
SALEM, OREGON

Date Started 8/6/06 Completed 10/15/06

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1810 Date 10/31/06

Signed Dellmuff