

STATE OF OREGON
WATER SUPPLY WELL REPORT

CROO 55772

WELL I.D. LABEL# L 159847

START CARD # 1081602

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

4/21/2026

(1) LAND OWNER
Owner Well I.D. _____
First Name _____ Last Name _____
Company WESTRIDGE HOA
Address 2766 NW CENTURY DR
City PRINEVILLE State OR Zip 97754

(2) TYPE OF WORK New Well Deepening Conversion
 Alteration (complete 2a & 10) Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrld
Casing: _____
Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable Auger
 Reverse Rotary Other _____

(4) PROPOSED USE Domestic Irrigation Community
 Industrial/ Commercial Livestock Dewatering
 Thermal Injection Other _____

(5) BORE HOLE CONSTRUCTION Special Standard (Attach copy)
Depth of Completed Well 80.00 ft.
BORE HOLE
Dia From To Material From To Amt sacks/lbs
12 0 80 Bentonite Chips 0 19 40 S
Calculated 12.27
Calculated

Seal placement method: A B C D E Other: POURED DRY
Backfill placed from _____ ft. to _____ ft. Material _____
Filter pack from 19 ft. to 80 ft. Material PEA GRAVEL Size pea gravi
Explosives used: Type _____ Amount _____
Seal Placement Begin Date 4/3/2026 Begin Time 13 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	8	X	2	30	0.250	ST	X			
C	8		60	80	0.250	ST	X			

Temp casing Yes Dia _____ From+ _____ To _____

(7) PERFORATIONS/SCREENS
Perforations Method _____
Screens Type JOHNSON Material SS

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe Size
Screen	Casing	8	30	60	.035			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	104	52	63	4

Temperature 54 °F Lab analysis Yes By _____
Water quality concerns? Yes (describe below) TDS amount 172 ppm
From _____ To _____ Description _____ Amount _____ Units _____

(9) LOCATION OF WELL (legal description)
County CROOK Twp 14.00 S N/S Range 15.00 E E/W WM
Sec 28 NE 1/4 of the NE 1/4 Tax Lot 100
Tax Map Number _____ Lot _____
Lat _____ " or 44.33153000 DMS or DD
Long _____ " or -120.92724000 DMS or DD
 Street address of well Nearest address
ELLIOTT LN, PRINEVILLE, OR 97754

(10) STATIC WATER LEVEL

Existing Well / Pre-Alteration	Date	SWL(psi)	+	SWL(ft)
Completed Well	4/9/2026			8

Flowing Artesian? Dry Hole?

WATER BEARING ZONES Depth water was first found 10.00

SWL Date	From	To	Est Flow	SWL(psi)	+	SWL(ft)
4/9/2026	10	80	104			8

(11) WELL LOG Ground Elevation 2827.27 FT

Material	From	To
WB BROWN CLAY SOFT	0	13
BROWN CLAY	13	20
WB SMALL GRAVEL	20	23
WB LARGE GRAVEEL & GREEN CLAY	23	30
WB GRAY CLAY SOFT	30	35
WB GREEN CLAY SOFT	35	48
WB GREEN BROWN CLAY W/ GRAVEL	48	58
WB GREEN CLAY SILTY	58	80

Construction
Begin Date 3/24/2026 Begin Time 10 10 End Date 4/9/2026

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number 2096 Date 4/21/2026
Signed LANCE SINGHOSE (E-filed)


(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1720 Date 4/21/2026
Signed JACK ABBAS (E-filed)
Drilling Company: ABBAS WELL DRILLING

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CROO 55772

4/21/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP	Oregon Water Resources Department 725 Summer St NE, Salem OR 97301 (503)986-0900	
This map is supplemental to the WATER SUPPLY WELL REPORT		
LOCATION OF WELL		Well Label: 159847
Latitude: 44.33153000 Datum: WGS84		Printed: April 21, 2026
Longitude: -120.92724000		<small>DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.</small>
Township/Range/Section/Quarter-Quarter Section:		<small>Provided by well constructor</small>
WM14.00S15.00E28NENE		
Address of Well:		
ELLIOTT LN, PRINEVILLE, OR 97754		

