

STATE OF OREGON
WATER SUPPLY WELL REPORT

CROO 55807

WELL I.D. LABEL# L

160441

START CARD #

1083006

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/19/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name AMANDA & ROYCE JR Last Name PARKER

Company _____

Address 32954 SANDRIDGE RDCity LEBANON State OR Zip 97355**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal:

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other _____
(4) PROPOSED USE☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____
(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 479.00 ft.

BORE HOLE				SEAL				sacks/
Dia	From	To	Material	From	To	Amt		lbs
12	0	18.5	Bentonite	0	18.5	10	S	
8	18.5	479			Calculated	10.49		
					Calculated			

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: BENTONITE DRY

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 7/29/2026 Begin Time 13 15**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	8	☒	1.5	18.5	0.250	ST	☒			
L	6		4	479	0.188	ST	☒			

Temp casing ☐ Yes Dia _____ From + ☐ _____ To _____**(7) PERFORATIONS/SCREENS**Perforations Method Factory cut

Screens Type _____ Material _____

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Liner	6	439	479	.125	2.5	608	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	18		474	1

Temperature 59 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 172 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County CROOK Twp 16.00 S N/S Range 16.00 E E/W WMSec 24 SE 1/4 of the NE 1/4 Tax Lot 5700

Tax Map Number _____ Lot _____

Lat _____ " or 44.16902000 DMS or DD

Long _____ " or -120.75089000 DMS or DD

☒ Street address of well ☐ Nearest address

NO SITE ADDRESS 161624-A0-05700 SE GATLING WAY & WALTHER
LOOP PRINEVILLE, OR

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/30/2026			358
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 358.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/30/2026	358	479	18			358

(11) WELL LOGGround Elevation 4039.39 FT

Material	From	To
Top soil & lava cobble	0	1
Black basalt - hard	1	89
Black basalt - fractured	89	169
Black fractured w/ brown claystone seems	169	207
Brown rock congl/ claystone	207	232
Brown claystone	232	243
Fractured crevices - brown/ black lava	243	312
Gray rock - hard fractured	312	375
Basalt w/ tan clay seems	375	409
Black rock - fractured	409	479

Construction

Begin Date 7/29/2026 Begin Time 09 10 End Date 7/30/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2069 Date 8/4/2026Signed MEGAN NOBLITT (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1970 Date 8/19/2026Signed NEIL FAGEN (E-filed)Drilling Company: 541-548-1245

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CROO 55807

8/19/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 44.16902000 Datum: WGS84

Longitude: -120.75089000

Township/Range/Section/Quarter-Quarter Section:

WM16.00S16.00E24 SENE

Address of Well:

NO SITE ADDRESS 161624-A0-05700 SE GATLING WAY & WALTHER LOOP PRINEVILLE, OR

Well Label: 160441

Printed: August 4, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

