

#11

STATE OF OREGON WATER RESOURCES DEPT SALEM, OREGON WATER WELL REPORT (as required by ORS 537.765)

CROO 058

155/16E/4 acc 84712

(START CARD) #

(1) OWNER: Well Number: 0134 Name: Donald T. Stansford Address: P.O. Box 693 City: Wilsonville State: OR Zip: 97170

(2) TYPE OF WORK: [X] New Well [] Deepen [] Recondition [] Abandon

(3) DRILL METHOD [] Rotary Air [] Rotary Mud [X] Cable [] Other

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [X] Other: Heat pump water source

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No Depth of Completed Well: 285 ft. Explosives used [] [X] Type Amount

Table with columns: HOLE Diameter, SEAL From, To, Material, Amount. Handwritten entries: 12 0 45 Cement 2 yards, 8 45 285

How was seal placed: Method [] A [] B [] C [] D [] E [X] Other: Tarmic Pipe Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Handwritten entries for Casing: 8", 185, 250, 195, 250

(7) PERFORATIONS/SCREENS: [X] Perforations Method: Cutting torch [] Screens Type Material

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Handwritten entries: 175, 185, 200, 4x6, 8

(8) WELL TESTS: Minimum testing time is 1 hour [] Pump [X] Bailer [] Air [] Flowing Artesian Yield gal/min: 50 Drawdown: 25' Drill stem at Time: 1 hr.

Temperature of water: 60 Depth Artesian Flow Found: Was a water analysis done? [] Yes By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County: Crook Latitude Longitude Township: 15 North Range: 16 Section: 4 NE 1/4 NE 1/4 Tax Lot: 300 Lot Block Subdivision Street Address of Well (or nearest address): 3000 E. 3rd St Prineville, OR 97154

(10) STATIC WATER LEVEL: 30 ft. below land surface. Date: 10-22-90 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Handwritten entries: 175, 285, 150, 30

(12) WELL LOG: Table with columns: Material, From, To, SWL. Handwritten entries: Top Soil (0-5), Brown Clay (5-19), Gravel (19-28), Soft Clay (28-175), Gravel (175-195), Red Clay (185-250), Shale (250-260), Red Clay (260-280), Shale (280-285)

Date started: 10-11-90 Completed: 10-22-90

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. Signed: WWC Number Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. Signed: Orchis Top WWC Number: 444 Date: 10-22-90