

19

RECEIVED

34S/14W/20

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

Curry 1594

JAN - 3 1994

(START CARD) # 60853

(1) OWNER: Name Glen Swafford Address P.O. Box 621 City Gold Beach State Or Zip 97444

(2) TYPE OF WORK: [X] New Well [ ] Deepen [ ] Recondition [ ] Abandon

(3) DRILL METHOD: [X] Rotary Air [ ] Rotary Mud [ ] Cable [ ] Other

(4) PROPOSED USE: [X] Domestic [ ] Community [ ] Industrial [ ] Irrigation [ ] Thermal [ ] Injection [ ] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [ ] Yes [X] No Depth of Completed Well 60 ft. Explosives used [ ] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, Material, SEAL From, To, Amount sacks or pounds. Row 1: 10", 0, 20, Bentonite, 0, 25, 10. Row 2: 6", 20, 60.

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E [X] Other Poured Dryed Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6", +1, 60, .250, [X], [ ], [X], [ ].

Final location of shoe(s)

(7) PERFORATIONS/SCREENS: [ ] Perforations Method [ ] Screens Type Material

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner.

(8) WELL TESTS: Minimum testing time is 1 hour. [ ] Pump [ ] Bailer [X] Air [ ] Flowing Artesian. Yield gal/min: 30, Drawdown, Drill stem at: 60, Time: 1 hr.

Temperature of Water 50 Depth Artesian Flow Found Was a water analysis done? [ ] Yes By whom Did any strata contain water not suitable for intended use? [ ] Too little [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Curry Latitude Longitude Township 34S N or S. Range 14W E or W. WM. Section 20 1/4 1/4 Tax Lot 200 Lot Block Subdivision Street Address of Well (or nearest address) 36939 Hwy 101 Gold Beach, Or

(10) STATIC WATER LEVEL: 26 ft. below land surface. Date 10/22/93 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 54'

Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 54', 60', 30, 26.

(12) WELL LOG: Ground elevation

Table with columns: Material, From, To, SWL. Row 1: Brown Sandy Soil, 0, 17. Row 2: Blue Claystone, 17, 42. Row 3: Sand & Gravel, 42, 60, 26.

Date started 10/22/93 Completed 10/22/93

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed [Signature] WWC Number 709 Date 12/30/93

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 709 Date 12/30/93