

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED

MAR - 7 1995

WATER RESOURCES DEPT. (START CARD) #

3/5/15 w/ 32
31-15-32
71687

Instructions for completing this report are on the last page of this form. SALEM, OREGON

(1) OWNER:

Name Alex Ellis Well Number 335
Address PO Box 41
City Port Deford State OR Zip 97465

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 76'9"
Explosives used ☐ Yes ☒ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
12"	0	96	Bentonite	0	48	52 5x

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Poured from surface

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8"	+1	66'9"	160*	☐	☒	☒	☐
8"	73'9"	76'9"	160*	☐	☒	☒	☐
10"	+16	4'	250	☒	☐	☐	☐
Liner: Protective Casing				☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ Perforations Method Attached to Casing
☒ Screens Type Johnson V-wire Material Stainless Steel

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
66'9"	73'9"	1080		8"	Pipe	☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailor ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
82	2.3	78'	1 hr.
82	23' 4"	78	4

Temperature of water 52° Depth Artesian Flow Found
Was a water analysis done? ☐ Yes By whom
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
Depth of strata:

(9) LOCATION OF WELL by legal description:

County Curry Latitude Longitude
Township 31 N or S Range 15 E or W WM.
Section 32 SW 1/4 SE 1/4
Tax Lot 2600 Lot Block Subdivision
Street Address of Well (or nearest address) Airport Rd.

(10) STATIC WATER LEVEL:

13 ft. below land surface. Date 12/1/95
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 19'

From	To	Estimated Flow Rate	SWL
19	90	260	13'

(12) WELL LOG:

Ground Elevation +/- 300'

Material	From	To	SWL
Sandy Clay Tan	0	3	
Sand w/ clay Gray	3	14	
Clay w/ peat DK Brown	14	19	
Fine Gravel w/ clay Brown	19	22	13'
Gravel Med-Fine w/ sand	22	23	
Medium Brown			
Gravel Coarse-Fine Gray	23	36	
Gravel Med-Fine w/	36	41	
Sand Fine Brown			
Sand medium Brown	41	49	
Sand Medium w/ Gravel	49	54	
Medium-Fine Brown			
Sand med-Fine Gray BRN	54	64	
Sand med Gray w/ Gravel	64	69	
Gravel Coarse w/ Shell Gray	69	72	
Gray Silty Clay	72	80	
Wood w/ silty Clay Gray	80	83	
Gravel Coarse Gray Gran	83	90	
Silty Clay Gray	90	96	

Date started 12/14/94 Completed 3/3/95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed

Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number

Signed

Date