

CURR
50207

RECEIVED

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WATER RESOURCES DEPT.

Instructions for completing this report are on the last page of this form.

AUG 11 1997

WELL I.D.# L 10 307

(START CARD) # 103016

(1) OWNER:

Well Number _____

Name Joe Westby
Address PO Box 6341
City BROOKINGS State OR Zip 97415

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 120 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter From To Material From To (Sacks) or pounds
10 0 26 BENTONITE 0 26 96How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☐ Other Poured in Annular SpaceBackfill placed from 26 ft. to 120 ft. Material 1/2 DOWNGravel placed from 26 ft. to 120 ft. Size of gravel 1/2 DOWN

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: <u>6</u>	<u>+1</u>	<u>120</u>	<u>250</u>	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations Method Air Perforation
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
<u>40</u>	<u>120</u>	<u>1/4 x 1/2</u>	<u>150</u>			☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian
Yield gal/min Drawdown Drill stem at Time

<u>2</u>	<u>74</u>	<u>120</u>	<u>1 hr.</u>
----------	-----------	------------	--------------

Temperature of water 50 Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County CURRY Latitude _____ Longitude _____
Township 40 N or S Range 13 E or W. WM.
Section 23 1/4 SW 1/4 SW
Tax Lot 101 Lot SW Block SW SubdivisionStreet Address of Well (or nearest address) 18241 Gardner Ridge Road BROOKINGS OR

(10) STATIC WATER LEVEL:

46 ft. below land surface. Date 7-2-97
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 60'

From	To	Estimated Flow Rate	SWL
<u>60</u>	<u>62</u>	<u>1/2</u>	<u>46</u>
<u>100</u>	<u>101</u>	<u>1/2</u>	<u>46</u>
<u>110</u>	<u>112</u>	<u>1</u>	<u>46</u>

(12) WELL LOG:

Ground Elevation 1200

Material	From	To	SWL
<u>CLAY</u>	<u>0</u>	<u>4</u>	<u>46</u>
<u>CLAYSTONE (Brown)</u>	<u>4</u>	<u>20</u>	<u>46</u>
<u>CLAYSTONE Blue</u>	<u>20</u>	<u>120</u>	<u>46</u>

Date started 7-1-97 Completed 7-6-97

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Pat Cart WWC Number 599
Date 8-5-97

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Pat Cart WWC Number 599
Date 8-5-97