

RECEIVED

CURR
50660

JUN 06 2000

32-15-33

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)WATER RESOURCES DEPT.
SALEM, OREGONWELL I.D. # L 34009
START CARD # 123848

Instructions for completing this report are on the last page of this form

(1) OWNER:

Name Robert Klinker
Address PO Box 841
City Port Orford State OR Zip 97465Well Number 713

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 42' ft.
Explosives used ☐ Yes ☒ No Type Amount 700

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	43	Bentonite	0	26	195x

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other Poured from SurfaceBackfill placed from 26 ft. to 43 ft. Material 10/20

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 5"	+1	37	160#	☒	☒	☐	☐
6"	+14	9'	1250	☒	☐	☐	☐
(Protective Casing)				☐	☐	☐	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ Perforations Method Attached to Casing
☒ Screens Type Nagoka V-wire Material SS

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
37	42	10/14		5"	Pipe	☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump	☐ Bailer	☒ Air	☐ Flowing
Yield gal/min	Drawdown	Drill stem at	Time
10	-	42	1 hr.

Temperature of water 52° Depth Artesian Flow FoundWas a water analysis done? ☐ Yes By WRCDid any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored

Depth of strata:

WATER RESOURCES DEPT.
SALEM, OREGON

ORIGINAL - WATER RESOURCES DEPARTMENT COPY - CONSTRUCTOR SECOND COPY - CUSTOMER

(9) LOCATION OF WELL by legal description:

County Curry Latitude Longitude
Township 32 N or S Range 15 E or W WM.
Section 33 SW 1/4 SE 1/4
Tax Lot 400 Lot Block Subdivision
Street Address of Well (or nearest address) Cedar Terrace Port Orford

(10) STATIC WATER LEVEL:

31'6" ft. below land surface. Date 6/2/00
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 31'6"

From	To	Estimated Flow Rate	SWL
31'6"	41	+/- 10 GPM	31'6"

(12) WELL LOG:

Ground Elevation +/- 300'

Material	From	To	SWL
Topsoil	0	1	
Clay Brown	1	6	
Sandy Clay orange Brown	6	10	
Sandy Clay orange w/	10	11	
Fine Gravel			
Gravel Fine-med w/sand	11	25	
CRS - Fine Orange Brown			
Gravel Fine-med w/sand	25	35	
CRS - Fine Brown			
Gravel Fine-CRS w/sand	35	41	
CRS - Fine Orange Brown			
Sand Stone Brown	41	42	
Sandy Clay white w/	42	43	
Fine-med Gravel			

Date started 6/2/00 Completed 6/2/00

(bonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Bardon Well & Septic Co Inc Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number

Signed Jim Mack Sr. MGC Date 6/5/00

RECEIVED

JUL 19 2000