

RECEIVED

CURR 50860

31-15-8

STATE OF OREGON WATER SUPPLY WELL REPORT

MAY 07 2002

WELL I.D. # L 51173 START CARD # 123885

Instructions for completing this report are on the back page of this form.

(1) LAND OWNER Name Curry County Parks Address PO Box 1198 City Gold Beach State OR Zip 97444

(2) TYPE OF WORK [X] New Well [] Deepening [] Alteration [] Abandonment

(3) DRILL METHOD: [] Rotary Air [X] Rotary Mud [] Cable [] Auger [] Other

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [] Livestock [X] Other Public Park

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 43' ft.

Table with columns: HOLE Diameter, SEAL Material, Sacks or pounds. Row 1: 10" 0 42 Bentenite 0 27 195x

How was seal placed: Method [] A [] B [] C [] D [] E [X] Other Poured from Surface

Backfill placed from 27 ft. to 42 ft. Material 10/20

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Rows for 5" and 6" casings.

Drive Shoe used [] Inside [] Outside [] None Final location of shoe(s)

(7) PERFORATIONS/SCREENS: [X] Screens Method Attached to Casing Type Ogjicka V-wire Material SS

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 35 1/2", 42 1/2", 10/14, 1, 5", Pipe

(8) WELL TESTS: Minimum testing time is 1 hour

Table with columns: Yield gal/min, Drawdown, Drill stem at, Time. Row 1: 15, -, 42, 1 hr.

Temperature of water 52° Depth Artesian Flow Found Was a water analysis done? [X] Yes By whom B.W.T.S.

(9) LOCATION OF WELL by legal description: County Curry Latitude Longitude Township 31 N of S Range 15 E of W. W.M. Section 8 NW 1/4 SE 1/4 Tax Lot 500 Lot Block Subdivision Street Address of Well (or nearest address) 92850 Boice Cope Rd Langlois OR 97450

(10) STATIC WATER LEVEL: 18' ft. below land surface. Date 5/2/02 Artesian pressure lb. per square inch Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 18, 40, +/-15, 18'

(12) WELL LOG: Ground Elevation +/-100'

Table with columns: Material, From, To, SWL. Rows: Sandy Clay brown, Clay tan, Sandy Clay tan, Sand tan, Sand w/ Fine gravel tan, Sand Fine tan, Gravel Fine-med w/ sand, Fine-med brn, Gravel Fine-CRS w/, Sand Fine-med gray brn, Gravel Fine-med w/w/, Sandy Clay Orange, Gravel Fine-med w/ sand, Fine-CRS gray brn, Gravel Fine-CRS w/, Sand + Sandy Clay brn, Sandy Clay Gray w/, Fine Gravel

Date started 5/1/02 Completed 5/2/02

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards.

Signed Chris Keasoy WWC Number 1759 Date 5/2/02

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above.

Signed Jim Muehl & McWee WWC Number 1493 Date 5/3/02