

**STATE OF OREGON  
WATER SUPPLY WELL REPORT**  
(as required by ORS 537.765)

(WELL I.D.)# L **63597**

(START CARD) # **127635**

Instructions for completing this report are on the last page of this form.

*CURR 51027*

(1) OWNER: Well Number  
Name **ARRIOLA CRANBERRIES INC.**

Address **20 RIVERTON RD**  
City **COQUILLE** State **OR** Zip **97423**

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well **50** ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL				
Diameter	From	To	Material	From	To	Sacks or pounds	
12	0	50	BENT	25	0	39 SACKS	

How was seal placed: Method  A  B  C  D  E  
 Other **POURED**  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from **50** ft. to **25** ft. Size of gravel **PEE**

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8	2	30	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s)  
(7) PERFORATIONS/SCREENS:

Perforations Method \_\_\_\_\_  
 Screens Type **COOK** Material **S.S**

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
30	45	.060		8		<input type="checkbox"/>	<input type="checkbox"/>
45	50			8		<input checked="" type="checkbox"/>	<input type="checkbox"/>
30	25			8		<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
50	AIR TEST	50	1 hr.
50	TOTAL PUMP		48 HRS PUMP

Temperature of water **52** Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County **CURRY** Latitude **N 42.85222** Longitude **W 124.51222**  
Township **31** S Range **15** W WM.  
Section **32** NW 1/4 NW 1/4  
Tax Lot **700** Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) **NEXT TO 924978 AIRPORT RD**

(10) STATIC WATER LEVEL:  
**12** ft. below land surface. Date **9-19-03**  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found **12**

From	To	Estimated Flow Rate	SWL
12	45	50 GPM	12

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

Material	From	To	SWL
BLACK GRAY PEAT CLAY	0	6"	
BROWN SANDY CLAY MIX	6"	4	
BROWN SAND	4	5	
GRAY CLAY	5	5'6"	
BROWN SAND & CLAY	5'6"	6	
GRAY CLAY LEN'S	6	6'1"	
GRAY BROWN SAND FINE	6'1"	16	12
BRN SAND W GRAY CLAY LEN'S BRN	16	17'6"	
BLUE SAND FINE MED	17'6"	20	
BLUE SAND MED CRS	20	36	
BLUE SAND CRS W/SHELLS	36	38	
BLUE SAND & GRAVEL MED CRS	38	45	
BLUE GRAY SANDSTONE	45	50	

RECEIVED

OCT 14 2003

NOV 13 2003

WATER RESOURCES DEPT  
SALEM, OREGON

Date started **10-05-00** Completed **9-19-03**

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number \_\_\_\_\_  
Signed \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number **1381**  
Signed *Don Barry* Date **10-10-03**