

STATE OF OREGON

WATER SUPPLY WELL REPORT

(as required by ORS 537.765 & OAR 690-205-0210)

01-08-2009

WELL LABEL # L 91213

START CARD # 1004976

(1) LAND OWNER

Owner Well I.D. 1294

First Name Alex

Last Name Ellis

Company Blanco Bogs

Address PO Box 25

City Port Orford

State OR

Zip 97465

(2) TYPE OF WORK



New Well



Deepening



Conversion



Alteration (repair/recondition)



Abandonment

(3) DRILL METHOD



Rotary Air



Rotary Mud



Cable



Auger



Cable Mud



Reverse Rotary



Other

(4) PROPOSED USE



Domestic



Irrigation



Community



Industrial/ Commercial



Livestock



Dewatering



Thermal



Injection



Other

(5) BORE HOLE CONSTRUCTION

Special Standard



(Attach copy)

Depth of Completed Well 48.00 ft.

BORE HOLE

Dia	From	To	Material	From	To	Amt	sacks/ lbs
10	0	49	Bentonite	0	23	19	S

How was seal placed:

Method



A



B



C



D



E

☒ Other Pour from Surface

Backfill placed from ft. to ft. Material

Filter pack from 23 ft. to 49 ft. Material Sand Size 6/9

Explosives used: ☐ Yes Type Amount

(6) CASING/LINER

Casing	Liner	Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
☒	☐	6	☒	1	36	sdr21	☐	☒	☒	☐
☐	☐	6	☐	43	48	sdr21	☐	☐	☒	☐
☐	☐	8	☒	1.3	4	.250	☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)Temp casing ☐ Yes Dia From To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Johnson V-Wire

Material StainlessSteel

Perf/S cren	Casing/ Liner	Screen Dia	From	To	Scm/slot width	Slot length	# of slots	Tele/ pipe size
Screen		6	36	43	.075			6

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
60	16.6	48	2

Temperature 52 °F Lab analysis ☐ Yes ByWater quality concerns? ☐ Yes (describe below)

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County Curry Twp 31.00 S N/S Range 15.00 W E/W WM

Sec 32 NW 1/4 of the SW 1/4 Tax Lot 2200

Tax Map Number Lot

Lat ° ' " or DMS or DD

Long ° ' " or DMS or DD

☒ Street address of well ☐ Nearest address

92498 Airport Road, Sixes

(10) STATIC WATER LEVEL

Date SWL(psi) + SWL(ft)

Existing Well / Predeepening			
Completed Well	01-07-2009		18.3

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 18.33

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
01-06-2009	18.33	44	60		18.33

(11) WELL LOG

Ground Elevation 200

Material	From	To
Clay brown	0	3
Clay brown w/wood	3	4
Cemented sand red	4	5
Sand fine tan	5	9
Cemented sand tan	9	11
Sandy clay tan	11	13
Cemented sand tan w/wood	13	14
Wood w/sandy clay tan	14	16
Gravel f-m brown w/sandy clay white	16	20
Gravel f-m red green w/10% sandy clay white	20	23
Gravel f-m white green w/sand f-c brown	23	30
Gravel c-f w/sand c-f brown	30	37
Gravel c-f w/sand c-f brown green	37	44
Cemented gravel c-f brown	44	49

Date Started 09-18-2008

Completed 01-07-2009

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1759

Date 01-08-2009

Electronically Filed

Signed CHRISTOPHER L KERSEY (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1493

Date 01-08-2009

Electronically Filed

Signed JAMES A MACK SR (E-filed)

Contact Info (optional) BANDON WELL & PUMP COMPANY (541) 347-7867