

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

CURR 52728
10/20/2016

WELL I.D. LABEL# L 122738
START CARD # 1032585
ORIGINAL LOG #

(1) LAND OWNER
Owner Well I.D. 1622
First Name KYLE Last Name RINGER
Company TUTUTUN LODGE
Address 96550 N BANK ROGUE RIVER ROAD
City GOLD BEACH State OR Zip 97444

(2) TYPE OF WORK
New Well [X] Deepening [ ] Conversion [ ]
Alteration (complete 2a & 10) [ ] Abandonment(complete 5a) [ ]

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrd
Casing: [ ] [ ] [ ] [ ] [ ] [ ] [ ] [ ]
Material From To Amt sacks/lbs
Seal: [ ] [ ] [ ] [ ] [ ] [ ] [ ] [ ]

(3) DRILL METHOD
Rotary Air [X] Rotary Mud [ ] Cable [ ] Auger [ ] Cable Mud [ ]
Reverse Rotary [ ] Other [ ]

(4) PROPOSED USE
Domestic [ ] Irrigation [ ] Community [X]
Industrial/ Commercial [ ] Livestock [ ] Dewatering [ ]
Thermal [ ] Injection [ ] Other [ ]

(5) BORE HOLE CONSTRUCTION
Special Standard [ ] (Attach copy)
Depth of Completed Well 101.50 ft.
BORE HOLE
Dia From To Material From To Amt sacks/lbs
11 0 33 Bentonite Chips 0 33 27 S
6 33 102 Calculated 17.3

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E [ ]
[X] Other POUR FROM SURFACE
Backfill placed from ft. to ft. Material
Filter pack from ft. to ft. Material Size
Explosives used: [ ] Yes Type Amount

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount Actual Amount

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd
6 [X] 1.5 49.75 .250 [ ] [ ] [X] [ ]
4.5 [ ] 40 101.5 Sdr26 [ ] [ ] [ ] [X]
Shoe [ ] Inside [X] Outside [ ] Other Location of shoe(s) 49.75
Temp casing [ ] Yes Dia From To

(7) PERFORATIONS/SCREENS
Perforations Method Holt Perf / Circ saw
Screens Type Material
Perf/ Casing/ Screen Dia From To Scrn/slot Slot # of Tele/ pipe size
Perf Casing 6 35 42 .25 3 50 6
Perf Liner 4.5 43 101 .125 8 90 4.5

(8) WELL TESTS: Minimum testing time is 1 hour
Pump [ ] Bailer [ ] Air [X] Flowing Artesian [ ]
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
30 100 2
Temperature 53 °F Lab analysis [X] Yes By Bandon Well & Pump Co.
Water quality concerns? [ ] Yes (describe below) TDS amount 59 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County CURRY Twp 36.00 S N/S Range 14.00 W E/W WM
Sec 11 SW 1/4 of the NW 1/4 Tax Lot 400
Tax Map Number Lot
Lat " or 42.47638889 DMS or DD
Long " or -124.33694444 DMS or DD
Street address of well [X] Nearest address [ ]
96550 N BANK ROGUE RIVER RD., GOLD BEACH

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration [ ] [ ]
Completed Well 10/18/2016 [ ] 17
Flowing Artesian? [ ] Dry Hole? [ ]

Table with columns: SWL Date, From, To, Est Flow, SWL(psi), + SWL(ft). Row 1: 10/17/2016, 17, 47, 30, 17.

(11) WELL LOG
Ground Elevation 38.00
Material From To
Clay w/gravel,fractured rocl & wood 0 7
Sandstone w/claystone & basalt fractured 7 42
Clay gray 42 44
Sandstone w/claystone brown orange 44 47
Claystone gray 47 49
Basalt black 49 62
Claystone gray 62 73
Sandstone gray w/quartz 73 102

Date Started 10/12/2016 Completed 10/18/2016

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number Date
Signed


(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1493 Date 10/20/2016
Signed JAMES A MACK SR (E-filed)
Contact Info (optional) BANDON WELL & PUMP COMPANY 541-347-7867

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CURR 52728

10/20/2016

### Map of Hole

<b>STATE OF OREGON WELL LOCATION MAP</b>	<b>Oregon Water Resources Department</b> 725 Summer St NE, Salem OR 97301 (503)986-0900	
This map is supplemental to the WATER SUPPLY WELL REPORT		
<b>LOCATION OF WELL</b>	<b>Well Label: 122738</b>	
Latitude: 42.47638889 Datum: WGS84	<b>Printed: October 20, 2016</b>	
Longitude: -124.33694444	DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.	
Township/Range/Section/Quarter-Quarter Section: WM 36S 14W 11 SWNW	Provided by well constructor	
Address of Well: 96550 N BANK ROGUE RIVER RD., GOLD BEACH		

