

STATE OF OREGON
WATER SUPPLY WELL REPORT

CURR 53461

WELL I.D. LABEL# L

160766

START CARD #

1082803

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/17/2026

(1) LAND OWNER

Owner Well I.D. 2288

First Name MEGHAN & DAVID Last Name PIETILA

Company _____

Address 500 BRETT WAYCity GRANTS PASS State OR Zip 97526**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal:

(3) DRILL METHOD☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Reverse Rotary ☐ Other _____**(4) PROPOSED USE**☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other _____**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)Depth of Completed Well 87.25 ft.

BORE HOLE			SEAL			sacks/lbs	
Dia	From	To	Material	From	To	Amt	
10	0	28	Bentonite Chips	0	28	15	S
6	28	124			Calculated	13.16	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POUR FROM SURFACEBackfill placed from 87.25 ft. to 124 ft. Material HOLE COLLAPSEDFilter pack from ft. to ft. Material Size Explosives used: ☐ Type Amount Seal Placement Begin Date 7/16/2026 Begin Time 14 30**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	1.83	38.5	0.250	ST	☒		OUT.	38.67
L	4.5		15.25	95	SDR26	PL	☒			

Temp casing ☐ Yes Dia From + To **(7) PERFORATIONS/SCREENS**Perforations Method Circular SawScreens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
		4.5	55	95	.125	8	50	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	0.5		85	1

Temperature 55 °F Lab analysis ☐ Yes By Water quality concerns? ☐ Yes (describe below) TDS amount 187 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County CURRY Twp 35.00 S N/S Range 11.00 W E/W WMSec 29 NE 1/4 of the NE 1/4 Tax Lot 102Tax Map Number Lot Lat ° ' " or 42.52459000 DMS or DDLong ° ' " or -124.02893000 DMS or DD☒ Street address of well ☐ Nearest address4630 OLD HOUSE CREEK RD. AGNESS**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/16/2026			69.66
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 70.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/16/2026	70	73	0.5			69.66

(11) WELL LOGGround Elevation 913.21 FT

Material	From	To
Dirt & boulders	0	2
Clay brown	2	6
Schist green, brown & gray	6	20
Serpentine green & brown	20	38
Basalt dk gray	38	39
Serpentine blue, gray & green	39	44
Schist gray & green mh	44	45
Serpentine blue green	45	46
Claystone gray h	46	48
Serpentine blue, green & gray ms	48	50
Serpentine gray & green mh	50	55
Serpentine blue green ms	55	62
Serpentine gray green fractured m	62	73
Schist dk brown & green mh	73	79
Serpentine green, brown & blue	79	124

Construction

Begin Date 7/14/2026 Begin Time 12 00 End Date 7/16/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1759 Date 7/17/2026Signed CHRISTOPHER KERSEY (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1493 Date 7/17/2026Signed JAMES MACK SR (E-filed)Drilling Company: Bandon Well & Pump Co. (541) 347-7867 J

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CURR 53461

7/17/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 42.52459000 Datum: WGS84

Longitude: -124.02893000

Township/Range/Section/Quarter-Quarter Section:
WM35.00S11.00W29NENE

Address of Well:

4630 OLD HOUSE CREEK RD. AGNESS

Well Label: 160766

Printed: July 17, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

