

**WATER WELL REPORT**  
STATE OF OREGON

**RECEIVED**

JAN 7 1981

State Well No. 3/S/5w-32da

State Permit No. ....

WATER RESOURCES DEPT  
SALEM, OREGON

**CURR 000978**

**(1) OWNER:**

Name Roy Peters  
Address Route 2, Box 160  
City Bandon State Ore

**(2) TYPE OF WORK (check):**

New Well  Deepening  Reconditioning  Abandon

If abandonment, describe material and procedure in Item 12.

**(3) TYPE OF WELL:**

Rotary Air  Driven  Domestic  Industrial  Municipal   
Rotary Mud  Dug  Irrigation  Test Well  Other   
Cable  Bored  Thermal: Withdrawal  Reinjection

**(4) PROPOSED USE (check):**

**CASING INSTALLED:** Steel  Plastic   
Threaded  Welded

..... 8" Diam. from ..... 0 ft. to 31'-9" ft. Gauge ..... 2.50  
....." Diam. from ..... ft. to ..... ft. Gauge .....

**LINER INSTALLED: No**

....." Diam. from ..... ft. to ..... ft. Gauge .....

**(6) PERFORATIONS:**

Perforated?  Yes  No

Type of perforator used .....  
Size of perforations ..... in. by ..... in.  
..... perforations from ..... ft. to ..... ft.  
..... perforations from ..... ft. to ..... ft.  
..... perforations from ..... ft. to ..... ft.

**(7) SCREENS:**

Well screen installed?  Yes  No

Manufacturer's Name Johnson  
Type Stainlesssteel Model No. telescope  
Diam. 8 Slot Size .035 Set from 30'-4" ft. to 32 ft.  
..... Slot Size .010 Set from 42 ft. to 52 ft.

**(8) WELL TESTS:**

Drawdown is amount water level is lowered below static level

Was a pump test made?  Yes  No If yes, by whom?  
Yield: ..... gal./min. with ..... ft. drawdown after ..... hrs.  
Air test ..... gal./min. with drill stem at ..... ft. .... hrs.  
Bailer test 30 gal./min. with 12 ft. drawdown after 1 hrs.  
Artesian flow ..... g.p.m.  
Temperature of water 52 Depth artesian flow encountered .....

**(9) CONSTRUCTION:**

Special standards: Yes  No

Well seal—Material used Cement  
Well sealed from land surface to 19 ft.  
Diameter of well bore to bottom of seal 12 in.  
Diameter of well bore below seal 8 in.  
Number of sacks of cement used in well seal 31 sacks  
How was cement grout placed? Pumped via tremie pipe

Was pump installed? No Type ..... HP ..... Depth ..... ft.  
Was a drive shoe used?  Yes  No Plugs ..... Size: location ..... ft.  
Did any strata contain unusable water?  Yes  No  
Type of Water? ..... depth of strata .....  
Method of sealing strata off .....  
Was well gravel packed?  Yes  No Size of gravel: .....  
Gravel placed from ..... ft. to ..... ft.

**(10) LOCATION OF WELL:**

County Curry Driller's well number .....  
NE 1/4 SE 1/4 Section 32 T. 31s R. 15w W.M.  
Tax Lot # ..... Lot ..... Blk ..... Subdivision .....

Address at well location: Sixes Airport Road  
Sixes, Ore.

**(11) WATER LEVEL: Completed well.**

Depth at which water was first found 8 ft.  
Static level 8 ft. below land surface. Date 12-23-80  
Artesian pressure ..... lbs. per square inch. Date .....

**(12) WELL LOG:**

Diameter of well below casing ..... 0 .....

Depth drilled 58 ft. Depth of completed well 52 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Sand medium tan	0	19	
Sand with peat lumps tan	19	23	
Sand with fine gravel blue	23	41	
Sand medium blue	41	48	
Sand with fine gravel brown	48	50	
Gravel fine brown	50	51	
Sand medium with fine gravel	51	52	
Sand fine brown	52	54	
Sand fine silty blue	54	58	

Work started 12-16 19 80 Completed 12-23 19 80  
Date well drilling machine moved off of well 12-23 19 80

**Drilling Machine Operator's Certification:**

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.  
[Signed] Andrew W. Miller Date 1-5, 1981  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 469

**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Bill Miller Well Drilling  
(Person, firm or corporation) (Type or print)  
Address Route 1, Box 1115, Bandon, Ore.

[Signed] Andrew W. Miller  
(Water Well Contractor)

Contractor's License No. 600 Date 1-5, 19 81

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date of well completion.

SP\*12658