

DESC 2100

DESC 2100

#1

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy  
of this report are to be  
filed with the  
STATE ENGINEER, SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

RECEIVED  
NOV 18 1967  
STATE OF OREGON  
(Please type or print)  
STATE ENGINEER  
OREGON  
G-4843

RECEIVED #1  
JUN 20 1967  
State Well No. 14/12-18dea  
OREGON  
State Permit No.

(1) OWNER: BOB RIEMENSCHNEIDER  
Name DOUBLE R.C. RANCH  
Address RT-1 BOX 236  
TERREBONNE ORE.

(2) LOCATION OF WELL:  
County DESC. Driller's well number  
Bearing and distance from section or subdivision corner  
SEC-18-T 14 S-RANGE-12 E.

(3) TYPE OF WORK (check):  
New Well  Deepening  Reconditioning  Abandon   
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):  
Domestic  Industrial  Municipal  Irrigation  Test Well  Other   
(5) TYPE OF WELL:  
Rotary  Cable  Dug  Driven  Jetted  Bored

(6) CASING INSTALLED:  
12" Diam. from 0 ft. to 232 ft. Gage 250  
24" Diam. from 0 ft. to 16 ft. Gage 312

(7) PERFORATIONS:  
Type of perforator used CUTTING TORCH  
Size of perforations 1/8 in. by 3 in.  
150 perforations from 170 ft. to 232 ft.

(8) SCREENS:  
Well screen installed?  Yes  No  
Manufacturer's Name  
Model No.  
Slot size Set from ft. to ft.  
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:  
Well seal—Material used in seal  
Depth of seal ft. Was a packer used?  
Diameter of well bore to bottom of seal 24 in.  
Were any loose strata cemented off?  Yes  No  
Was a drive shoe used?  Yes  No  
Was well gravel packed?  Yes  No Size of gravel 1/4 in. to 3/4  
Gravel placed from 160 ft. to 232 ft.  
Did any strata contain unusable water?  Yes  No  
Type of water? depth of strata  
Method of sealing strata off

(10) WATER LEVELS:  
Static level 170 ft. below land surface Date 11-12-66  
Artesian pressure lbs. per square inch Date

(11) WELL TESTS: Drawdown is amount water level is lowered below static level  
Was a pump test made?  Yes  No If yes, by whom? EASTERN ORE.  
Yield: 2000 gal./min. with NO ft. drawdown after 20 hrs.  
Bailer test 100 gal./min. with NO ft. drawdown after 3 hrs.  
Artesian flow g.p.m. Date  
Temperature of water 56 Was a chemical analysis made?  Yes  No

(12) WELL LOG: Diameter of well below casing CASED TO BOTTOM  
Depth drilled 232 ft. Depth of completed well 232 ft.  
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
OVER BURDEN	0	5
SANDSTONE	5	45
RED CLINDERS	45	70
BOULDER CONG.	70	120
SANDSTONE	120	171
WATER BEARING BLACK SAND MIXED WITH LARGE RIVER AGGREGATE	171	232

Work started 10-28 1966 Completed 11-12 1966  
Date well drilling machine moved off of well 11-14 1966

(13) PUMP:  
Manufacturer's Name NONE  
Type: H.P.

Water Well Contractor's Certification:  
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
NAME JACKSON DRILLING SERVICE  
(Person, firm or corporation) (Type or print)  
Address REDMOND ORE.  
Drilling Machine Operator's License No. 370  
[Signed] Thomas D. Jackson  
(Water Well Contractor)  
Contractor's License No. 442 Date 11-17 1966



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

POA 1, Well #1

RECEIVED

Do not complete if the well already has a Well Identification Number.

DEC 11 2017

WATER RESOURCES DEPT
SALEM, OREGON

I. OWNER INFORMATION

Current Owner Name (please print): BIG FALLS RANCH CO. (REX BARBER)
Mailing Address: P.O. Box 434
City, State, Zip: TERREBONNE, OR 97760
Mail Well ID Tag to: [ ] SAME AS ABOVE [ ] In Care Of (C/O)
Name & Address:
City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 14 (North / South) Range: 12 (East / West) Section: 18 SW 1/4 of the SE 1/4
Tax Lot (usually last 3-5 numbers of Tax Map #): 1406 County DESCHUTES
GPS Coordinates: 44.35252, -121.33788
Street Address of Well, City: 70505 LOWER BRIDGE WAY, TERREBONNE, OR
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): IRRIGATION
Date Well Constructed (or property built): 11/14/1966 Total Well Depth: 232' Casing Diameter: 12"
Owner at time the well was constructed (if known): BOB REIMENSCHNEIDER Well Log # (if known):
Other Information: POA #1, WELL #1

SUBMITTED BY (please print): WILLIAM D. NASHUM - Well Inspector - SCIR
PHONE: 541/639-4109 EMAIL &/or FAX:

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

12-11-17

Well Log Number:

DESC 2100

Well Identification #:

#L122705