

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97301 within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON (Please type or print) (Do not write above this line)

State Well No. 14/L3-10

State Permit No.

(1) OWNER:

Name L. NISBET
Address Redmond Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 22 ft. Gage 250
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 277 ft. below land surface Date 9, 1, 1969
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield:	gal./min. with	ft. drawdown after	hrs.
"	"	"	"
"	"	"	"

Bailer test 20 gal./min. with 8 ft. drawdown after 2 hrs.
Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Bentonite
Depth of seal 20 ft.
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County DESC Driller's well number
1/4 1/4 Section 10 T. 14 S. R. 13 E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 330 ft. Depth of completed well 330 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Overburden	0	8	
Rock	8	104	
Sandstone	104	209	
Rock	209	253	
Sandstone	253	330	277

Work started 8-22 1965 Completed 9, 1, 1969

Date well drilling machine moved off of well 9, 2, 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Cecil P. Tackel Date 9, 5, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 139

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Horst Well Drilling
(Person, firm or corporation) (Type or print)

Address 836 512th Redmond Ore

[Signed] Cecil P. Tackel
(Water Well Contractor)

Contractor's License No. 318 Date 9, 5, 1969