

NOV 01 1989

155/11E/8
StartCard # 7138

STATE OF OREGON
WATER WELL REPORT (as required by ORS 537.765)
WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name Bob Lambert
Address 11405 S.W. Cardinal Terrace
City Beaverton State Oregon Zip 97005

Well Number: _____

(2) TYPE OF WORK:

☐ New Well ☒ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 412 ft.
Explosives used Yes ☐ No ☐ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12"	0	27'	Bentonite	0	27'	15 sacks
8"	27'	412'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other poured down

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+2	27'	.250	☒	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☒ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
10		406	1 hr.

Temperature of water 52* Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom noDid any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other no

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Deschutes Latitude _____ Longitude _____
Township 15S N or S, Range 11E E or W, WM.
Section 08 1/4 1/4
Tax Lot 00400 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 68496 George Cyrus Rd

(10) STATIC WATER LEVEL:

412 ft. below land surface. Date 10-27-89

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 378'

From	To	Estimated Flow Rate	SWL
378'	412'	20 GPM	378'

(12) WELL LOG:

Ground elevation unknown

Material	From	To	SWL
Top Soil & Boulders	0	20	
Hard Grey Basalt	20	42	
Mild Brown Basalt	42	45	
Hard Grey Basalt	45	47	
Orange Conglomerate	47	56	
Brown Sandstone	56	102	
Yellow Sandstone	102	110	
Brown Sandstone	110	128	
Green Brown Sandstone	128	185	
Brown Conglomerate	185	205	
Mild Black Basalt	205	230	
Hard Grey Basalt	230	268	
Mild Black Basalt	268	273	
Hard Grey Basalt	273	302	
Hard Grey Basalt	302	378	
Water-Bearing Basalt	378	412	

Date started Oct. 19, 1989 Completed Oct. 27, 1989

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed [Signature] WWC Number 1276
Date 10-30-89

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 608
Date 10-30-89