

RECEIVED

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

DESC
50174

MAR 26 1996

(START CARD) #

82315

Instructions for completing this report are on the last page of this form.

WATER RESOURCES DEPT.

SALEM, OREGON

(1) OWNER: Patricia Alexander
Name: Patricia Alexander
Address: P.O. Box 779
City: LA Pine State: ORE Zip: 97739

Well Number

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well: 30 ft.
Explosives used ☐ Yes ☒ No Type: Amount:

HOLE			SEAL			Sacks	pounds
Diameter	From	To	Material	From	To		
10"	0'	18'	Bentonite	0'	18'	6 1/2	
6"	18'	30'					

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other
Backfill placed from _____ ft. to _____ ft. Material:
Gravel placed from _____ ft. to _____ ft. Size of gravel:

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	1'	30'	.250	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s): 11/4

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
19'	29'	1/8"	114	3"		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
20	3'		1 hr.

Temperature of water: 50° Depth Artesian Flow Found:
Was a water analysis done? ☐ Yes By whom:
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other:
Depth of strata:

(9) LOCATION OF WELL by legal description:

County: Deschutes Latitude: Longitude:
Township: 22 S N or S Range: 10 E E or W. WM.
Section: 03 SE, 1/4 NW, 1/4
Tax Lot: 05300 Lot: Block: Subdivision:
Street Address of Well (or nearest address): 16041 Wadwell Rd
LA PINE, ORE 97739

(10) STATIC WATER LEVEL:

11 ft. below land surface. Date: 3/15/96
Artesian pressure: lb. per square inch. Date:

(11) WATER BEARING ZONES:

Depth at which water was first found: 15'

From	To	Estimated Flow Rate	SWL
15	20	5 gpm	11
20	30	20+	11

(12) WELL LOG:

Ground Elevation:

Material	From	To	SWL
PUMICE	0	5	
SAND	5	15	11
SAND & GRAVEL	15	20	11
FINE GRAVEL	20	30	11

Date started: 3/15/96 Completed: 3/15/96

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number:

Signed: Date:

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number: 1664

Signed: Date: 3/15/96