

RECEIVED

DESC 50198

STATE OF OREGON WATER SUPPLY WELL REPORT

APR 11 1996

(START CARD) # 82316

Instructions for completing this report are on the last page of WATER RESOURCES DEPT.

(1) OWNER: John Wilson Well Number _____
Name John Wilson
Address 16254 PINE DROP LN.
City LAPINE State ORE Zip 97739

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 40 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0'	18'	Bentonite	0'	18'	6
6"	18'	40'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	1'	40'	.250	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) NA

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
29'	39'	1/8"	114	3"		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
20	2'		1 hr.

Temperature of water 50° Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Deschutes Latitude _____ Longitude _____
Township 21S N or S Range 10E E or W. WM. _____
Section 22 SW 1/4 NE 1/4 _____
Tax Lot 01400 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 16254 PINE DROP LN., LAPINE, ORE 97739

(10) STATIC WATER LEVEL:

21 ft. below land surface. Date 3/22/96
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 21'

From	To	Estimated Flow Rate	SWL
21'	30'	3 gpm	21
30'	40'	20 gpm	21

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
PUMICE	0	3	
GRAVEL	3	10	
SAND	10	21	
SAND & GRAVEL	21	40	21

Date started 3/22/96 Completed 3/22/96
(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
WWC Number 1664
Signed James A. May Date 3/22/96