

WATER SUPPLY WELL REPORT

DESC 52733

Received Date 12/08/1999

Well ID Tag # L 30805

Start Card # 121647

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(1) OWNER

Well Number

Name TYLER SAUNDERS

Street 1213 SE TEAKWOOD

City BEND State OR Zip 97702

(2) TYPE OF WORK

- ☒ New ☐ Alter (Recondition) ☐ Alter (Repair)
☐ Deepening ☐ Abandonment

(3) DRILL METHOD

- ☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

Other

(4) PROPOSED USE

- ☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation ☐ Injection
☐ Livestock ☐ Thermal Other

(5) BORE HOLE CONSTRUCTION

Special Standards ☐ Depth of completed well 810 ft.Explosives Used ☐ Amount Type

Diameter	From	To
12.00	0.00	18
8.00	18.00	752
6.00	752.00	810

Material	Begin Depth	End Depth	Material Amount	Units
Bentonite	0.00	18.00	17.00	B

How as seal placed: Method

Other POURED DRY

Backfill placed from ft. TO ft. Material

Filter pack from ft. TO ft. Size in.

(6) CASING/LINER

Casing or Liner	Diameter	Begin Depth	End Depth	Gauge	Material	Weld	Threaded	Location Of Shoe
C	8.00	2.00	18.00	.250	S			
L	6.00	0.00	752.00	.188	S			

(7) PERFORATION/SCREENS

☐ Perforation: Method☐ Screens Type Material

(8) WELL TESTS (Minimum testing time is 1 hour)

Type Yield Units Drawdown Stem at Duration
 Air 20.0 G 800 1.0

Temperature of water 53 °F/C Depth artesian flow found ft.

Was water analysis done? ☐

By Whom?

Did any strata contain water not suitable for intended use? ☐ Too Little ☐ Salty☐ Muddy ☐ Odor ☐ Colored Other

Depth of strata ft.

(9) LOCATION OF HOLE By legal description

County Deschutes Latitude Longitude

Township 18.00 S Range 13.00 E Subdivision

Tax lot 601 Lot Block

Section 8 SE 1/4 NW 1/4

Street Address of Well (or nearest address)

61485 GOSNEY RD

MAP with location indentified must be attached

(10) STATIC WATER LEVEL

705.0 Ft. below land surface. Date 10/06/1999

Artesian Pressure lb/sq. in. Date

(11) WATER BEARING ZONES

Depth at which water was first found 745 ft.

From	To	Est. Flow Rate	SWL
745	790	20	705

(12) WELL LOG

Ground Elevation ft.

Material	From	To	SWL
LOAM, COBBLES	0	8	
LAVA GRAY	8	85	
LOST CIRC 3 YRDS CEMENT	85	170	
LAVA	170	188	
LAVA FRAC LAYERS CINDERS	188	192	
LAVA BROWN	192	208	
LOST CIRC 4 YRDS	208	270	
LAVA GRAY	270	320	
BASSALT RED	320	360	
LAVA/CINDERS	360	375	
LAVA GRAY	375	426	
CEMENT 5 YRDS	426	436	
CINDERS	436	445	
LAVA	445	480	
LAVA FRAC/CINDERS	480	530	
LAVA GRAY	530	545	
LOST CIRC(CAVE?)	545	752	
NO CIRC	752	785	
LAVA/BASALT FRAC	785	800	
CINDERS/LAVA	800	810	
BASALT	810	705	

Date started 11/29/1999

Completed 12/06/1999

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to the best knowledge and belief.

Signed By JACK ABBAS

(bonded) Water Well Constructor Certification: WWC Number 1720

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 758

Signed By THOMAS R PECK

D-3 WELL DRILLING