

DESC 53172
DESC 53172STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 20430

START CARD # 131773

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number #1
Name VALUABLE LAND INC.
Address 750 W 3rd STREET
City PRINEVILLE State OR Zip 97754

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 472 ft.
Explosives used ☐ Yes ☒ No Type - Amount -

HOLE SEAL
Diameter From To Material From To Sacks or pounds
12 0 19 BENTONITE 0 19 13 SACKS
8 19 472
8 19 472

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other POURED DOWN DRY
Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 8 +1 19 250 ☒ ☐ ☐ ☐
Liner: 6 -12 472 188 ☒ ☐ ☒ ☐

Final location of shoe(s) NO SHOE USED

(7) PERFORATIONS/SCREENS:
☒ Perforations Method MACHINE CUT
☐ Screens Type SLOT Material STEEL
From To Slot size Number Diameter Tele/pipe size Casing Liner
432 472 4x4 300 6 - ☐ ☒

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing
Yield gal/min Drawdown Drill stem at Time
60 - 470 1 hr.

Temperature of water 58° Depth Artesian Flow Found
Was a water analysis done? ☒ Yes ☐ No
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
Depth of strata: SEP 12 2000

(9) LOCATION OF WELL by legal description:
County DESCHUTES Latitude Longitude
Township 15 N or S Range 13 E or W. WM.
Section 30 n e 1/4 n w 1/4
Tax Lot 905 Lot Block Subdivision
Street Address of Well (or nearest address)

OFF WICKUP DRIVE
(10) STATIC WATER LEVEL:
339 ft. below land surface. Date 7-6-00
Artesian pressure - lb. per square inch. Date -

(11) WATER BEARING ZONES:
Depth at which water was first found 430

From	To	Estimated Flow Rate	SWL
410	472	60+GPM	339

(12) WELL LOG:
Ground Elevation

Material	From	To	SWL
SANDY SOIL	0	3	
BROWN LAVA	3	68	
RED SS CONG	68	80	
TAN CONG	80	105	
BROWN CONG	105	145	
GREY LAVA	145	165	
TAN SS CONG	165	180	
RED SS	180	190	
TAN SS CONG	190	210	
GREY LAVA	210	298	
RED LAVA -VOID	298	305	
TAN SS CONG	305	410	
BROWN SAND & GRAVEL	410	472	339

RECEIVED

JUL 13 2000

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 6-27-00 SALEM, OREGON 7-6-00

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number
Signed Date

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction date reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
WWC Number 1556
Signed Date 7-7-00

ORIGINAL & FIRST COPY WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER
SALEM, OREGON