

Instructions for completing this report are on the last page of this form

(START CARD) # 101980

Well Number: **W01**

City **San Luis Obispo** State **CA** Zip **93405**

☒ New Well ☐ Deepening ☐ Alteration (repair/reconstruction) ☐ Abandonment

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

☒ Domestic	☐ Community	☐ Industrial	☐ Irrigation
☐ Thermal	☐ Injection	☐ Livestock	☐ Other

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 365 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Poured Dry

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+2	38	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	6"	0	360	.188	☒	☐	☒	☐
					☐	☐	☐	☐

☒ Perforations Screens		Method	Factory		Material		
	To	Slot size	Number	Diameter	Tel./pipe size	Casing	Liner
0	360	3/16"	480			☐	☒
						☐	☐
						☐	☐
						☐	☐
						☐	☐

☒ Pump ☐ Boiler ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
60	5'	365	1 hr.

Temperature of Water 61 Depth Artesian Flow found 2

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Demography and education

County Deschutes Latitude _____ Longitude _____
Township 16S N or S. Range 11E E or W. of W.M.
Section 9 SE 1/4NW 1/4
Tax Lot 500 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) _____
66295 Hwy. 20, Bend, OR 97701

283 ft. below land surface. Date 6/6/97

Artesian pressure lb. per square inch. Date

Depth at which water was first found 283

From	To	Estimated Flow Rate	SWL
283	303	15	283
303	335	10	283
342	365	75-80	340

Ground elevation

Material	From	To	SWL
Sandy Top Soil	0	5	
Brown Pumice	5	18	
Red Cinders	18	33	
Brown Basalt	33	73	
Black Sandstone	73	80	
Brown Sandstone Cong.	80	93	
Tan Conglomerate	93	100	
White Pumice	100	143	
Gray Basalt	143	180	
Red Cinders caving	180	187	
Gray Basalt Hard	187	190	
Gray Sandstone	190	200	
Brown Broken Basalt	200	243	
Red Cinder Gravel	243	268	
Gray Basalt Hard	268	283	
Brown Sandstone & Gravel WB	283	303	283
Gray Basalt Broken WB	303	335	283
Brown Sandstone WB	335	342	283
Red Cinder Gravel WB	342	365	283

RECEIVED

~~JAN 30 2002~~

~~WATER RESOURCES DEPT.~~
~~SALEM, OREGON~~

Date started 6/4/97 Completed 6/6/97

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WESTERN WATER DEVELOPMENT

Signed _____ P.O. Box 1670 WWC Number _____
Redmond, OR 97756 Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Robert Buckner WWC Number 1385
Date 6-13-97
Western Water Development Corporation