

STATE OF OREGON  
Water Supply Well Report

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

DESC 56248

DESC

Received Date: 08-31-2004

Well ID Tag # L 70669

Start Card # 167172

(1) Owner

Well Number:

Name: SCOTT SMITH

Street: 69500 CROOKED HORSESHOE RD

City: SISTERS State: OR Zip Code: 97759

(2) Type of Work

- ☒ New ☐ Alter (Recondition) ☐ Alter (Repair)  
☐ Deepening ☐ Abandonment

(3) Drill Method

- ☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger  
Other:

(4) Proposed Use

- ☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation ☐ Injection  
☐ Livestock ☐ Thermal Other:

(5) Bore Hole Construction

- ☐ Special Standards: Depth of completed well: 250.00 ft.  
☐ Explosives Used: Amount: Type:

| Hole     |       |        | Seal |       |       |           |
|----------|-------|--------|------|-------|-------|-----------|
| Diameter | From  | To     | Mtrl | From  | To    | Sacks/lbs |
| 12.00    | 0.00  | 58.50  | CE   | -2.00 | 58.50 | 66        |
| 8.00     | 58.50 | 250.00 | BC   | 0.00  | 2.00  | 1         |

How was seal placed? C Other: POURED DRY

Back fill placed from: Material:

Filter pack from: Size:

(6) Casing / Liner

| Csng/<br>Liner | Diameter | From   | To     | Gauge | Mtrl | Weld | Thrd | Shoe<br>at | Shoe<br>used |
|----------------|----------|--------|--------|-------|------|------|------|------------|--------------|
| C              | 8.00     | 1.50   | 58.50  | .250  | S    | X    |      |            |              |
| L              | 6.00     | -10.00 | 250.00 | .188  | S    | X    |      |            |              |

(7) Perforation / Screens

| Perforations: |        |        |       |        |        |      |         |              |         |
|---------------|--------|--------|-------|--------|--------|------|---------|--------------|---------|
| Mtrl          | From   | To     | Width | Height | #Slots | Dia. | t/pSize | Csng/<br>Lnr | Method  |
| S             | 230.00 | 250.00 | 0.13  | 3.00   | 216    | 6.00 |         | L            | MACHINE |

| Screens: |      |    |        |        |      |         |      |       |
|----------|------|----|--------|--------|------|---------|------|-------|
| Mtrl     | From | To | S Size | #Slots | Dia. | t/pSize | Type | Gauge |

(8) Well Tests (Minimum testing time is one hour)

| Type | Yield | Units | Drawdown | Stem at | Duration |
|------|-------|-------|----------|---------|----------|
| A    | 40.00 | G     |          | 250.00  | 1.00     |

Temperature of Water: 51 F

Was water analysis done? ☐ Depth of artesian flow:  
by whom?

Did any strata contain water unsuitable for use? ☐ Too Little ☐ Salty

☐ Muddy ☐ Odor ☐ Colored other:

Depth of strata:

(9) Location of Hole by legal description

County: DESC Latitude: Longitude:

Township: 15.00 S Range: 12.00 E

Section: 11 NWSE Lot: 0 Block: 0

Tax Lot: 701 Subdivision: PP199-53

Street Address of Well (or nearest address):

74TH REDMOND

MAP, with location identified, must be attached.

(10) Static Water Level

Feet below land surface: 193.0 Date: 08 / 18 / 2004

Artesian Pressure: Date:

(11) Water Bearing Zones

Depth at which water was first found: 205.00 ft.

| From   | To     | est Flow | swl |
|--------|--------|----------|-----|
| 205.00 | 250.00 | 40.00    | 193 |

(12) Well Log

Ground Elevation:

| Material               | From   | To     | swl |
|------------------------|--------|--------|-----|
| SAND PUMICE GRAVEL     | 0.00   | 35.00  |     |
| SANDSTONE              | 35.00  | 68.00  |     |
| LAVA                   | 68.00  | 128.00 |     |
| SANDSTONE              | 128.00 | 205.00 |     |
| CONGLOMERATE SANDSTONE | 205.00 | 250.00 | 193 |

Date Started: 08 / 17 / 2004

Date Completed: 08 / 18 / 2004

(unbonded) Water Well Constructor Certification:

I certify that the work I perform on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to the best knowledge and belief.

Signed by: ALLEN R PECK

WWC #: 1831

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed by: JACK ABBAS

WWC #: 1720

ABBAS WELL DRILLING CO

Phone: 541-548-2787