

DESC 58209
RECEIVEDSTATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

SEP 06 2007

WELL I.D. # L 85915
START CARD # W 191906

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name Dwight Tantan
Address 700 Box 2573
City LaPine, Or State OR Zip 97739(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other _____(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 50 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
10"	0'	18'	Bent	0'	18'	10 50' Sacks
6"	18'	50'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other PouredBackfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	0'	30'	.250	☒	☐	☒	☐
Liner: 4 1/2"	90'	50'	SDR 26	☐	☒	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS

☒ Screens Type Fele Material PVC

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
30'	50'	2"	5640	1010	4 1/2"	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
10 GPM	20'		1 Hr

Temperature of water 47 Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County Deschutes
Tax Lot 1900 Lot _____
Township 22 N or S Range 9 E or W WM
Section 25C 1/4 _____ 1/4 _____
Lat 43° 13' 16" or _____ (degrees or decimal)
Long 121° 35' 86" or _____ (degrees or decimal)

Street Address of Well (or nearest address)

50530 Deer St.

(10) STATIC WATER LEVEL

10' ft. below land surface. Date 9-1-07

_____ ft. below land surface. Date _____

Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found 25'

From	To	Estimated Flow Rate	SWL
23'	30'	106 GPM	10'

(12) WELL LOG

Ground Elevation 4303

Material	From	To	SWL
Pumice	0'	3'	
Cemented Clay & Sand	4'	12'	
Clay	12'	15'	
Fine Sand	15'	21'	
Clay	21'	23'	
Fine Sand	23'	45'	10'
Cemented Sand & Clay	45'	50'	

Date Started 8-29-07 Completed 9-1-07

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____

Date 9-1-07Signed Chad Whitely

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1842Date 9-1-07Signed Chad Tantan