

WATER WELL REPORT
STATE OF OREGON

RECEIVED

FEB 15 1985

WATER RESOURCES DEPT
SALEM, OREGON

State Well No. 20S/10E-13dd

State Permit No.

(1) OWNER:

Name Chuck Cramer
Address PO Box 6856
City Bend OR State 97707

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐
Rotary Mud ☐ Dug ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal: ☐ Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☐ Plastic ☒
Threaded ☐ Welded ☒

5" Diam. from 1 ft. to 60 ft. Gauge schedule 125
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name shop made
Type slotted Model No.
Diam. 5" Slot Size 200 Set from 55 ft. to 60 ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Is a pump test made? ☒ Yes ☐ No If yes, by whom Driller
Field: 20 gal./min. with 0 ft. drawdown after 12 hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 43 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used 55 ft. cement

Well sealed from land surface to ft.

Diameter of well bore to bottom of seal in.

Diameter of well bore below seal in.

Number of sacks of cement used in well seal 11 sacks

How was cement grout placed? pressure & mix

Was pump installed? Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Deschutes Driller's well number
SE 1/4 SE 1/4 Section 13 T. 20S R. 10E W.M.
Tax Lot # Lot Blk Subdivision
Address at well location: Upland Drive

(11) WATER LEVEL: Completed well,

Depth at which water was first found 55 ft.
Static level 0 ft. below land surface. Date 11-17-84
Artesian pressure 0 lbs. per square inch. Date 11-17-84

(12) WELL LOG:

Diameter of well below casing

Depth drilled 60 ft. Depth of completed well 60 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Decomposed Material	0	3	
Brown clay	3	17	
Soft Brown clay	17	25	
Green clay	25	47	
Brown clay	47	55	
Loose sand & gravel	55	60	0

Work started 10-25-1984 Completed 11-17 1984

Date well drilling machine moved off of well 11-17 1984

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] John J. Lawton Date 11-17, 1984

Bonded Water Well Constructor Certification:

Bond (number) Issued by: Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name (Person, firm or corporation) (Type or print)

Address

[Signed] John J. Lawton Water Well Constructor

Date , 19

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*45292-690