

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

DESC 62612

5/5/2021

WELL I.D. LABEL# L

START CARD #

ORIGINAL LOG #

Page 1 of 2

142005
1051576

(1) LAND OWNER

Owner Well I.D.

First Name FRED

Last Name SZKOTIK

Company

Address P.O BOX 8299

City BEND

State OR

Zip 97708

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrld

Material	From	To	Amt	sacks/lbs					

Seal: Dia + From To Gauge Stl Plstc Wld Thrld

Material	From	To	Amt	sacks/lbs					

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 337.00 ft.

BORE HOLE			SEAL			sacks/	
Dia	From	To	Material	From	To	Amt	lbs
12	0	25	Bentonite	0	25	17	S
8	25	340			Calculated	14.18	
					Calculated		

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other DRY BENTONITE

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Yes Type Amount

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

Casing	Liner	Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrld
☒	☐	8	☒	2	38	.250	☒	☐	☒	
☐	☒	6	☐	8	337	.188	☒	☐	☒	
☐	☐		☐				☐	☐	☐	
☐	☐		☐				☐	☐	☐	
☐	☐		☐				☐	☐	☐	
☐	☐		☐				☐	☐	☐	

Shoe ☐ Inside ☒ Outside ☐ Other Location of shoe(s) 337

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Material

Perf/	Casing/	Screen	Screen	Liner	Dia	From	To	Scrn/slot	Slot	# of	Tele/
								width	length	slots	pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
25		330	1

Temperature 54 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 70 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County DESCHUTES Twp 15.00 S N/S Range 11.00 E E/W WM

Sec 32 NW 1/4 of the SE 1/4 Tax Lot 300

Tax Map Number Lot

Lat ° ' " or 44.22553915 DMS or DD

Long ° ' " or -121.43992079 DMS or DD

☒ Street address of well ☐ Nearest address

17895 2ND STREET BEND OREGON 97703

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	4/23/2021			258
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 258.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
4/23/2021	258	340	25			258

(11) WELL LOG

Ground Elevation

Material	From	To
Top soil cobble rock	0	6
brown ss tuff	6	75
lava rock	75	80
brown ss tuff	80	95
lava rock	95	101
brown ss tuff	101	115
lave rock congl	115	190
brown ss congl	190	213
lava rock hard 16yds sg cement 50/260	213	220
brown ss	220	235
pink ss	235	239
broken lava brown lava congl	239	270
broken cinders lava congl	270	340

Date Started 4/21/2021

Completed 4/23/2021

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1970 Date 5/5/2021

Signed NEIL FAGEN (E-filed)

Contact Info (optional) 541-548-1245

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

DESC 62612

5/5/2021

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 44.22553915 Datum: WGS84

Longitude: -121.43992079

Township/Range/Section/Quarter-Quarter Section:

WM15.00S11.00E32NWSE

Address of Well:

17895 2ND STREET BEND OREGON 97703

Well Label: 142005

Printed: May 5, 2021

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

