

Amd 9/24/2026
STATE OF OREGON
WATER SUPPLY WELL REPORT

DESC 65837

WELL I.D. LABEL# L

Page 1 of 3

162376

START CARD #

1083422

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/3/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name _____ Last Name _____

Company CANNON FAMILY TRUST

Address 15770 GREENWOOD

City LA PINE State OR Zip 97739

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☐ Cable ☒ Auger

☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 94.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	94	Bentonite Chips	0	18	13	S
					Calculated	10	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED

Backfill placed from 18 ft. to 89 ft. Material SAND

Filter pack from 89 ft. to 94 ft. Material FILTER SAND Size 10/20

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 9/3/2026 Begin Time 09 30

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+ From To Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒ 1 19 0.250	ST	☒			
L	4	☐ 5 89 SDR26	PL	☒			

Temp casing ☐ Yes Dia _____ From + _____ To _____

(7) PERFORATIONS/SCREENS

Perforations Method _____

Screens Type slotted Material pvc

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Liner	4	89	94	.1		1750	Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	20	6	85	1

Temperature 48 °F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below) TDS amount 49 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County DESCHUTES Twp 22.00 S N/S Range 10.00 E E/W WM

Sec 4 NE 1/4 of the SW 1/4 Tax Lot 2400

Tax Map Number _____ Lot _____

Lat _____ " or 43.69271949 DMS or DD

Long _____ " or -121.53626575 DMS or DD

☒ Street address of well ☐ Nearest address

15770 GREENWOOD, LA PINE, OR 97739

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	9/3/2026			30
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 30.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
9/2/2026	30	94	20			30

(11) WELL LOG

Ground Elevation 4249.94 FT

Material	From	To
topsoil	0	1
pumie	1	4
gravel	4	6
coarse brown sand	6	9
coarse dark brown sand	9	17
fine dark brown sand	17	23
fine black sand	23	44
black silt	44	82
fine black sand	82	94

Construction

Begin Date 9/2/2026 Begin Time 10 00 End Date 9/3/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2020 Date 9/3/2026

Signed TYLER MATHERS (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1528 Date 9/3/2026

Signed STEVE MATHERS (E-filed)

Drilling Company: mathers drilling

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

--

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

DESC 65837

9/3/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 43.69271949 Datum: WGS84

Longitude: -121.53626575

Township/Range/Section/Quarter-Quarter Section:
WM22.00S10.00E4NESW

Address of Well:

15770 GREENWOOD, LA PINE, OR 97739

Well Label: 162376

Printed: September 3, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

