

WATER WELL REPORT

STATE OF OREGON

DESC

7697

RECEIVED
FEB 15 1985
WATER RESOURCES DEPT.
SALEM, OREGON
PLEASE TYPE OR PRINT IN INK

State Well No.

215/11E-3266

State Permit No.

(1) OWNER:

Name Dean Bryant
 Address 47831 Elgin
 City Schubert State OR

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐
 Rotary Mud ☐ Dug ☐
 Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
 Irrigation ☐ Test Well ☐ Other ☐
 Thermal: Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☐ Plastic ☒
 Threaded ☐ Welded ☐
 5" Diam. from +1 ft. to 80 ft. Gauge Sched. 135
 " Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in by in.
 perforations from ft. to ft.
 perforations from ft. to ft.
 perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☒ Yes ☐ NoManufacturer's Name HydrophylisType PVC Model No.Diam. 5" Slot Size 070 Set from 70 ft. to 80 ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☒ Yes ☐ No If yes, by whom? DullinRecord: 12 gal./min. with 7 ft. drawdown after 4 hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 44 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☐Well seal—Material used CementWell sealed from land surface to 18 ft.Diameter of well bore to bottom of seal 5 in.Diameter of well bore below seal 5 in.Number of sacks of cement used in well seal 6 sacksHow was cement grout placed? pressure grout

Was pump installed? Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Deschutes Driller's well number
 NW 1/4 NW 1/4 Section 32 T. 21S R. 11E W.M.
 Tax Lot # Lot Blk Subdivision

Address at well location:

Gossett Loop - Newberry Est

(11) WATER LEVEL: Completed well.

Depth at which water was first found 68 ft.Static level 68 ft. below land surface. Date 9/29/84

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing

Depth drilled ft. Depth of completed well ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
<u>Sandy Loam</u>	<u>0</u>	<u>3</u>	
<u>Brn. sand</u>	<u>3</u>	<u>37</u>	
<u>White pumice & sand</u>	<u>37</u>	<u>52</u>	
<u>Brown sand</u>	<u>52</u>	<u>68</u>	
<u>Brown sand & gravel</u>	<u>68</u>	<u>80</u>	<u>68</u>

Work started 9/28 1984 Completed 9/29 1984Date well drilling machine moved off of well 9/29 1984

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date, 19

Bonded Water Well Constructor Certification:

Bond EX-190687 Issued by: Ames. State
 (number) Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name John S. Lawson DrillingAddress 17289 Sprague River, Bend, OR[Signed] John S. Lawson 97707

Water Well Constructor

Date 9/29 1984

NOTICE TO WATER WELL CONSTRUCTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
 SALEM, OREGON 97310

within 30 days from the date of well completion.

SP*45292-690