

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

DESC
8840

155/12E/10ac

(START CARD) # 53898 labeled

(1) OWNER: Well Number _____
Name Jerry & Yvette Moore
Address 1170 NW 91 st
City Redmond State Ore Zip 97756

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 300 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
12"	0 25	bentonite	25 0	23 sacks	
8"	25 285				
5"	285 300				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other poured

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+1	25	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	6"	-5	285	.188	☒	☐	☒	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method machine
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
265	285	228	1/8 by 3			☐	☒
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
20 +		300	1 hr.

Temperature of Water 52 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Des Latitude _____ Longitude _____

Township 15 S N or S. Range 12 E E or W. WM.

Section 10 SW 1/4 NE 1/4

Tax Lot 605 Lot _____ Block _____ Subdivision _____

Street Address of Well (or nearest address) _____

1170 NW 91st Redmond, Ore

(10) STATIC WATER LEVEL:

206 ft. below land surface. Date 9-8-93

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 204

From	To	Estimated Flow Rate	SWL
204	300		206

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
brn soil	0	2	
med to crse gravel brn sand	2	10	
gray basalt	10	34	
brn basalt	34	43	
brn clayey ss	43	61	
gray congl fine	61	104	
brn congl crse	104	136	
tan ss	136	204	
grayish brn congl fine(WB)	204	222	
brn sand fine gravel			
(pumice (WB))	222	263	
crse gray congl (WB)	263	275	
red cindery congl (WB)	275	300	

Date started 9-3-93 Completed 9-8-93

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed D. R. Day WWC Number 1575
Date 9-12-93

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed John V. Johnson WWC Number 595
Date 9-12-93