

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(WELL ID.) # **L 89837**

(START CARD) # **188838**

(1) **OWNER:** Well Number _____
 Name **STEVE SCHOEDER**
 Address **1883 SCOTTSBURG W. ROAD**
 City **SCOTTSBURG** State **OR** Zip **97473**

(2) **TYPE OF WORK:**
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) **DRILL METHOD:**
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) **PROPOSED USE:**
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) **BORE HOLE CONSTRUCTION:**
 Special Construction approval ☐ Yes ☒ No Depth of Completed Well **100** ft.
 Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10	0	24	BENTONITE	0	24	13
6	24	100				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other **POURED FROM SURFACE**

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

		Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:						☐	☐	☐	☐
		6	+1	28		☒	☐	☒	☐
Liner:						☐	☐	☐	☐
		4 1/2	0	100	adr28	☐	☒	☒	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:									
☒ Perforations		Method SAW							
☐ Screens		Type _____		Material _____					
From	To	Slot size	Number	Diameter	Telephone size	Casing	Liner		
20	100	1/4 X 0.00		4 1/2		☐	☒		
						☐	☐		
						☐	☐		
						☐	☐		

(8) **WELL TESTS:** Minimum testing time is 1 hour

		☐ Pump	☐ Bailor	☒ Air	☐ Flowing
Yield gal/min	Drawdown	Drill stem at		Time	
8		88		1 hr.	
				1 HR	

Temperature of water **51 degrees** Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) **LOCATION OF WELL by legal description:**

County **DOUGLAS** Latitude _____ Longitude _____
 Township **22** S Range **10** W WM.
 Section **13** SE 1/4 SW 1/4
 Tax Lot **488** Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) **WELL AT 1883 SCOTTSBURG W. ROAD, SCOTTSBURG, OR 97473**

(10) **STATIC WATER LEVEL:**

31 ft. below land surface. Date **1-28-04**

Artesian pressure _____ lb. per square inch. Date _____

(11) **WATER BEARING ZONES:**

Depth at which water was first found **44**

From	To	Estimated Flow Rate	SWL
44	46	1 GPM	
70	72	7 GPM	

(12) **WELL LOG:**

Ground Elevation **88' ABOVE SL**

Material	From	To	SWL
GRAVEL FILL	0	1	
BROWN SAND STONE WITH CLAY MIX	1	12	
SOFT BROWN SAND STONE	12	23	
GRAY SAND STONE	23	100	
RECEIVED JAN 28 2004 WATER RESOURCES DEPT SALEM, OREGON			

Date started **01-23-04**

Completed **01-26-04**

(unbonded) **Water Well Constructor Certification:**

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed **Kenn S Hardy** WWC Number **1888** Date **01-28-04**

(bonded) **Water Well Constructor Certification:**

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed **John Hylt** WWC Number **1736** Date **01-26-04**