

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
MAY 7 1964
STATE ENGINEER

WATER WELL REPORT

DOUG

006036

State Well No. 27/5W-6Q
State Permit No.

(1) OWNER:

Name DAN. PARKER
Address ROSEBURG ORE

(2) LOCATION OF WELL:

County DOUGLAS Driller's well number 100
S.W. 1/4 S.E. 1/4 Section 6 T. 27S R. 5W W.M.
Bearing and distance from section or subdivision corner
308 58 ROSEBURG ORCHARD CO.
TRACT 1 PLAT 1

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 31 ft. Gage 1/4
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used MILLS
Size of perforations 1/8 in. by 4 in.
100 perforations from ft. to ft.
perforations from ft. to ft.
40 perforations from 18 1/2 ft. to 30 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal CEMENT
Depth of seal 1.5 ft. Was a packer used? NO
Diameter of well bore to bottom of seal 9 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 4 ft. below land surface Date 5-5-64
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 15 gal./min. with 18 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 35 ft. Depth of completed well 35 ft.

Formation: Describe by color, character, size of material and structure, and
show thickness of aquifers and the kind and nature of the material in each
stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
BLACK soil	0	6 ft
RED GRAVELLY CLAY	6	22
BLUE CLAY HARD PAN	22	22 1/2
RED LAVA CLAYSTONE SOFT	22 1/2	30
RED LAVA ROCK HARD	30	35

Work started 5-4 1964 Completed 5-5 1964

Date well drilling machine moved off of well 5-5 1964

(13) PUMP:

Manufacturer's Name

Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME BOEHRS & WALTON
(Person, firm or corporation) (Type or print)

Address BOX 414 OAKLAND ORE,

Drilling Machine Operator's License No. 29-30

[Signed] E. L. Boehrs
(Water Well Contractor)

Contractor's License No. 267 Date 5-7 1964

(USE ADDITIONAL SHEETS IF NECESSARY)