

RECEIVED
GILL 277

15/218/3B

AUG 30 1995

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPARTMENT (START CARD) # 78370
SALEM, OREGON

GILL
277

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number _____
Name Gary Wilde
Address 18048 Middle Rock Creek Lane
City Arlington State OR Zip 97812

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 530 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
14"	0	19	Cement	0	19	14 sacks
10"	19	530				

How was seal placed: Method A B C D E
 Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Casing/Liner	Diameter	From	To	Gauge	Material			
					Steel	Plastic	Welded	Threaded
Casing:	10"	+1	19	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 19

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Tele/pipe size	Material	
						Casing	Liner
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min 1,000+ Drawdown _____ Drill stem at 530 Time 1 hr.

Temperature of water 62° Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Gilliam Latitude _____ Longitude _____
Township 1S N or S Range 21E E or W. WM. _____
Section 3 1/4 NW 1/4 _____
Tax Lot 203 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Olex, OR
(near Arlington, OR)

(10) STATIC WATER LEVEL:
124 ft. below land surface. Date 6-27-95
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 396

From	To	Estimated Flow Rate	SWL
396	412	100	124
525	530	1,000+	124

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
Clay soil	0	2	
Brown clay	2	6	
Brown basalt	6	12	
Gray basalt	12	127	
Green clay	127	139	
Gray basalt	139	227	
Black basalt	227	232	
Gray basalt	232	396	
Brown basalt	396	412	WB
Black basalt	412	429	
Gray basalt	429	525	
Brown basalt with yellow soapstone	525	530	WB

Date started 6-21-95 Completed 6-27-95
(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1218
Signed Patrick Wallace Date 7-15-95



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owrd

Application for
Well ID Number

RECEIVED

NOV 14 2018

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

OWRD

Current Owner Name (please print): Gary Wilde
Mailing Address: 18048 Middle Rock Creek Lane
City, State, Zip: Arlington, OR 97812
Mail Well ID to: [X] SAME AS ABOVE [] In Care Of (C/O)
Name & Address:
City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 1 S (North / South) Range: 21 E (East / West) Section: 3 1/4 of the NW 1/4
Tax Lot (usually last 3-5 numbers of Tax Map #): 203 County Gilliam
GPS Coordinates: Lat: 45.50518D, Long -120.17897D
Street Address of Well, City: 18048 Middle Rock Creek Lane, Arlington, OR 97812
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation Supplemental (IS)
Date Well Constructed (or property built): 6-27-1995 Total Well Depth: 530 ft Casing Diameter: 10"
Owner at time the well was constructed (if known): Gary Wilde Well Report # (if known): GILL 277
Other Information:

SUBMITTED BY (please print): John A. Short / Water Right Services, LLC
PHONE: 541-389-2837 EMAIL &/or FAX: johnshort@usa.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date: 11-14-18 Well Report Number: GILL 277 Well Identification #: L-132428

GILL 277

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.50518000 Datum: WGS84

Longitude: -120.17897

Township/Range/Section/Quarter-Quarter Section:

WM 1S 21E 3 SESW

Address of Well:

18048 MIDDLE ROCK CR LN, ARLINGTON, OR 97812

Revised: 18048 MIDDLE ROCK CR LN

Well Label: L132428

Well Log: GILL 277

Printed: November 21, 2018

DISCLAIMER: This map is intended to represent the approximate location of the exempt use well provided by the land owner. It is not intended to be construed as survey accurate in any manner.

Generated by OWRD Staff

